

CADD Details Library

Report 1
Architectural Details

Approved For Public Release; Distribution Is Unlimited

Library of CADD Details

Report 1 Architectural Details

Report 2 Mechanical Details

Report 3 Electrical Details

Report 4 HTRW Details

Report 5 Structural Details

Report 6 Civil/Site Details

The contents of this report are not to be used for advertising, publication, or promotional purposes. Citation of trade names does not constitute an official endorsement or approval of the use of such commercial products.

The findings of this report are not to be construed as an official Department of the Army position, unless so designated by other authorized documents.

CADD Details Library

Report 1 Architectural Details

by Tri-Service CADD/GIS Technology Center

U.S. Army Engineer Research and Development Center Waterways Experiment Station 3909 Halls Ferry Road Vicksburg, MS 39180-6199

Report 1 of a Series

Approved for public release; distribution is unlimited

Waterways Experiment Station Cataloging-in-Publication Data

CADD details library / by Tri-Service CADD/GIS Technical Center.

- 6 v. : ill.; 28 cm. (Technical report; CADD-93-1 repts.1-6 1999) Includes bibliographical references.
- rept. 1. Architectural details (updated)—rept. 2. Mechanical details (updated)—rept. 3. Electrical details (updated)—rept. 4. HTRW details (updated)—rept. 5. Structural details—rept. 6. Civil/Site details—rept.
- 1. Computer-aided design. 2. Computer-aided engineering. 3. Architectural drawing —Detailing Computer programs. I. United States. Army. Corps of Engineers. II. U.S. Army Engineer Research and Development Center. III. Tri-Service CADD/GIS Technology Center (U.S.) IV. Title: Architectural details. V. Series: Technical report (U.S. Army Engineer Research and Development Center); CADD-93-1 repts.1-6 1999. TA7 W34 no.CADD-93-1 repts.1-6 1999

Contents

Summaryiv						
Prefacevi						
1—Introduction						
2—CADD Details Library						
Library Creation2Detail Integrity2Creating a Detail2Detail Naming4						
3—CADD Detail Manager						
Introduction9Startup9CADD Detail Manager Setup10CADD Detail Manager Use11Other Installation Options11						
4—Design/Construction Field Working Group						
5—Index of Details						
6—Inch-Pound Library						
7—Metric Library						
Appendix A: Abbreviations for CADD Details Library						
Appendix B: Metric Construction Information						
Appendix C: Detail Revision/Deletion Recommendation Form						
SF 298						

Summary

Several years ago, before computer-aided design and drafting (CADD) became the standard drafting tool in design, a seasoned draftsman might require, on the average, 40 hours to develop a sheet of construction details by hand. Through the use of CADD, the effort of creating a single detail has been reduced considerably. Once the designer has created a detail using CADD tools, he/she can save the detail to a file and use the detail over and over in different construction projects. Eventually, the designer will have compiled a library of details that he/she will consistently use. These details can be easily inserted into a detail sheet and then modified to meet the project requirements and specifications. This development and reuse of CADD details represents a considerable time-savings tool to the designer.

When the Tri-Service CADD/GIS Technology Center (the Center) was established in 1992, one of the first tasks was the compilation of a CADD Details Library utilizing details created by tri-service personnel. The Center did not expend design funds to hire an architect/engineer or use in-house resources to develop completely new details; instead these tri-service details were organized into a generic format and cataloged by type.

To further simplify the use of the details library, the former Architectural Automation Field Working Group (AAFWG) tasked the Center to develop an icon-driven software retrieval system. Developed using MDL and AutoLISP programming, the retrieval software

ran on both MicroStation and AutoCAD platforms using UNIX, DOS, Windows, Windows NT, and Windows 95 operating systems.

Typically, detailing on a design project does not begin prior to the 35-percent design phase. At the 35-percent phase, the designer has defined the building's structure and envelope requirements and is ready to begin selecting typical project details.

After reviewing details in hardcopy or electronic format and identifying usable details, the designer/draftsman initiates the "CADD Detail Manager" program. The designer scrolls through the details listing, identifies the desired detail, reviews it within the display box, selects the required scale, and then places it on the detail sheet. This process is repeated until the entire sheet is filled. Simple modifications to the details in order to meet specific job requirements/ specifications complete the sheet. The designer may call up the CADD Detail Manager while in any design file, thus enabling detail placement anywhere within a set of drawings.

The CADD Details Library should always be considered a "living" library. Since the conception of the idea for this project, this philosophy has proven to be true. In 1995 the Center released the first CADD Details Library CD-ROM to enthusiastic response. The first CD-ROM contained over 1,200 details representing the Architectural; Mechanical; Electrical; and Hazardous, Toxic,

and Radioactive Waste disciplines. User demand resulted in the addition of Civil/Site, Structural, Interior Design, and Landscape Architectural details to the current edition of the CADD Details CD-ROM. With the push toward using the metric system in the tri-services, 100 of the architectural details contained in the first CD-ROM were converted to metric format. Because of the desire for a "paperless" environment, all documents related to the current version of the CADD Details Library have been released totally in electronic format on the CD-ROM. This gives the designer the option of printing out only the documents (or only the pages) that he/she requires, thereby saving

printing costs for the Center. Through efforts such as these, the CADD Details Library will continue to grow to include all the design disciplines with costs incurred for technical review/modification, CD-ROM reproduction, and distribution.

It is the Center's hope that the efforts of the Center, with the backing of the former Field Working Groups and the currently existing Design/Construction Field Working Group, to develop comprehensive, multidiscipline sets of generic details will not only help designers in their daily work but also demonstrate the tri-service commitment to CADD productivity.

Preface

This report is the first volume of a series of reports consisting of architectural; mechanical; electrical; hazardous, toxic, and radioactive waste (HTRW); structural; and civil/site details. These reports are part of the Tri-Service CADD/GIS Technology Center's (the Center) initiative to develop a standard methodology for the development, documentation, and use of generic design details in computer-aided design and drafting (CADD) systems. By providing both a startup set of details and a menu-driven software retrieval program, the Center hopes to ensure easy accessibility to generic design details and encourage their use in the CADD environment.

It must be emphasized that the intent of this document is not to provide "Standard Details," but to furnish CADD users with a starting point for the development of project-specific details. Although reasonable efforts have been made to verify that the enclosed details are technically correct and meet existing, generally available building code requirements, there is no expressed or implied warranty of correctness or compliance. It is the final responsibility of the user/designer to ensure the accuracy, completeness, applicability, workability, and code compliance of all details whether used or misused in whole or in part.

Project Manager for the CADD Details Library was Stephen C. Spangler of the

Center. Original authors of the CADD Details Library reports were James T. Wilson and Stephen C. Spangler of the Center. Chief of the Center was Harold L. Smith. The Center is located in the Information Technology Laboratory (ITL), U.S. Army Engineer Waterways Experiment Station (WES), Vicksburg, MS, a complex of five laboratories of the U.S. Army Engineer Research and Development Center (ERDC). During preparation and publication of this report, Director of ITL was Dr. N. Radhakrishnan and Commander of ERDC was COL Robin R. Cababa, EN. This report was prepared and published at the WES complex of ERDC.

The Center would like to thank Mr. Stan Shirk, Omaha District, for his continued devotion and efforts to the CADD Details Library project. The Center would also like to recognize Mr. Todd Blakley, formerly of the Sacramento District, for his contributions as former chairman of the Design/Construction Field Working Group's (FWG) Details Subcommittee. A special acknowledgment goes to Mr. Stephen Goodin, South Atlantic Division, and Mr. Alain Bernier, Southwestern Division, for their support in the initial development of the details library concept.

The Tri-Service CADD/GIS Technology Center would like to acknowledge the contributions of the following sites who helped in submitting and/or formatting details for this release of the CADD Details Library.

Brooks Air Force Base

Department of Veterans Affairs

Naval Air Station, Fort Worth

NAVFACENGCOM, Western Division

Navy Public Works Center, Washington, D.C.

Tinker Air Force Base

U.S. Army Corps of Engineers, Charleston District

U.S. Army Corps of Engineers, Fort Worth District

U.S. Army Corps of Engineers, Little Rock District

U.S. Army Corps of Engineers, Mobile District

U.S. Army Corps of Engineers, Omaha District

U.S. Army Corps of Engineers, Pacific Ocean Division

U.S. Army Corps of Engineers, Pittsburgh District

U.S. Army Corps of Engineers, Sacramento District

U.S. Army Corps of Engineers, Seattle District U.S. Army Corps of Engineers, Transatlantic Programs Center

U.S. Army Engineering and Support Center, Huntsville

Design/Construction FWG Details Subcommittee

Stan Shirk (Chairman), U.S. Army Corps of Engineers, Omaha District

Elbert Godwin, U.S. Army Corps of Engineers, Fort Worth District

Mark Hall, Department of Veterans Affairs

Lee Meier, Scott Air Force Base, IL

Jerry Sakahara, U.S. Army Corps of Engineers, Sacramento District

Stephen Spangler, Tri-Service CADD/GIS Technology Center

Beneficial comments (recommendations, enhancements, deletions, etc.) which may be of use in improving this document should be addressed to:

U.S. Army Engineer Research and
Development Center, Waterways
Experiment Station
Tri-Service CADD/GIS Technology Center
ATTN: CEWES-ID-C/Spangler
3909 Halls Ferry Road
Vicksburg, MS 39180-6199

1 Introduction

The use of computer-aided design and drafting (CADD) systems within the Department of Defense (DoD) has produced an increase in design efficiency while netting an appreciable reduction in overall design cost. In some offices, a 30- to 40-percent reduction in design/drafting man-hours, over the traditional "on-the-board" design effort, has been realized. These improvements have been achieved through the utilization of discipline-specific CADD design packages, the sharing of CADD-developed project information, and the reuse of design information. Recognizing the increased productivity represented in the reuse and adaptation of design and construction details, the Tri-Service CADD/GIS Technology Center (the Center) initiated a project to collect and disseminate generic design details within the DoD.

Based on work completed by the former Mechanical Field Working Group in November 1991, and ongoing work by the former Electrical and Architectural Automation Field Working Groups, the Center recognized the necessity to pool the resources of all DoD design disciplines to ensure

consistency in detail development. Issues concerning scale, levels/layers, line thickness, text, colors, layout, naming convention, and file storage/retrieval procedures needed to be resolved to the satisfaction of all the design disciplines before the Center could continue. The Center tasked the former Architectural Automation Field Working Group to prepare applicable criteria and procedures for standardizing the development of the CADD Details Library.

In accordance with the Metric Conversion Act of 1975 (Public Law 94-168) as amended by the Omnibus Trade and Competitiveness Act of 1988 (Public Law 100-418), and Executive Order (EO) 12770 dated July 25, 1991, this and future editions of the CADD Details Library will include Standard International (metric) details. Appendix B contains information on changes that will occur in design drawings and construction as a result of the conversion to the metric system.

Chapter 1 Introduction 1

2 CADD Details Library

Library Creation

"Evolution" is the best description of the process for incorporating the suggested format for creating generic details. Agencies currently developing detail libraries are encouraged to begin incorporating the format into their daily design efforts, and not attempt a complete revamping of their existing detail libraries. As details are created, they should be included in the agency's detail library and submitted to the Center for possible inclusion in the DoD-wide master library. By no means should the CADD Details Library ever be considered a completed product. It is only the **beginning** of what should be a daily routine of adding and revising details for all design disciplines within the tri-services.

Detail Integrity

Although a liability disclaimer covering all the details is included as part of the CADD Details Library, each detail submitted for inclusion into the library should be reviewed by the submitting agency for integrity and compliance with current design criteria. It will be extremely helpful to the Center and the Design/Construction Field Working Group's Details Subcommittee if each detail is properly reviewed prior to submitting it for placement into the Library.

Creating a Detail

Graphics

When developing a detail, draw the detail at full size (1 inch = 1 inch (inch-pound) or 1 mm = 1 mm (metric)) (Figure 1). Each detail should exist in an individual drawing file, either in AutoCAD's .dwg or MicroStation's .dgn formats. MicroStation details should not be created as cells or as part of a cell library. AutoCAD details should not be saved as blocks or blocks written out to a file (wblocks).

For detail uniformity, a standard detail layout has been developed (Figures 2 and 3). This box is only a guide for laying out details; it is understood that not all details can fit into the layout. When producing details larger than the standard detail layout box, every effort should be made to follow the format as much as possible. For example, keep the detail origin and title in the lower left corner of the detail and try to use multiples of the standard detail layout box (2 high, 2 wide, etc.).

Working units

For MicroStation details, the working units should be set to 1:12:8000 (ft:in:PU) for inch-pound details and 1:1:10 (mm:none:PU) for metric details. For Auto-CAD details, the default "UNITS" setting should be "#4 Architectural" for inch-pound details and "#2 Decimal" for metric details.




Figure 1. Detail drawn at full size




Figure 2. Inch-pound detail layout box




Figure 3. Metric detail layout box

Levels/layers

The previous edition of the CADD Details Library proposed a level/layer scheme based on the pen weight at which graphics would be plotted. Feedback from the field indicated that this was too restrictive and unclear. Users want to be able to "turn off" individual components of a detail versus all items drawn at a certain line weight. For instance, a designer may want to be able to turn off the CMU in a detail but not the reinforcing rebar.

As a result of this input, levels/layers for details have been developed for Release 1.8 of the Tri-Service A/E/C CADD Standard (Table 1). Levels/layers are grouped into the most common construction materials/items required to create a particular discipline's details.

Color/line widths

The primary purpose of color is to provide a drawing with visual depth and clarity or, in some CADD systems, to assign plotted line widths. The previous edition of the CADD Details Library established a specific color and line weight to each level/layer. Users found this guideline to be too restrictive. Often a user will want to show items on the same level/layer at different line weights to emphasize particular parts of a detail over others. As a result, the user may use any of the colors shown in Table 2 to create details. However, the line weights shown in the table beside each color have to be associated with that color in order to ensure that details are plotted at the correct visual weight.

Patterning/hatching

Patterning/hatching should be added to the detail on level/layer A-ANNO-PATT (Figure 4). When the detail is being patterned or hatched, only the default pattern or hatch libraries supplied with MicroStation or Auto-CAD should be used.

Text

After the scale of the detail is determined, text should be placed at heights corresponding to Tables 3 and 4. This ensures that all notes and dimensions will be plotted at a height of 1/8 inch (3 mm) and the detail title will be plotted at a height of 1/4 inch (6 mm). For example, in Figure 5, the notes should be placed at a height of 1/2 inch and the detail title should be placed at a height of 1 inch for a detail that is plotted at a scale of 3" = 1' - 0". The text style used for details should be Font 1 for MicroStation users and "ROMANS" for AutoCAD users.

Abbreviations

Abbreviations for words or phrases frequently used in details should be as noted in Appendix A. When possible, abbreviations should be kept to a minimum. Other abbreviations, particularly discipline-unique abbreviations, may be used but must not conflict with those in Appendix A.

Detail Naming

File names for the master set of details are based on *UniFormat* (Interim Edition) produced by the Construction Specifications Institute (CSI); *UniFormat* is used with permission from CSI. *UniFormat* may be purchased from CSI by calling (800)689-2900. Level 1 and Level 2 *UniFormat* categories are used for the first three alphanumeric characters of the file name. The Code, Sub-Code, Detail Number, and graphic type characters are non-*UniFormat* conventions developed specifically by the Center for the CADD Details Library file naming methodology (see Figure 6).

l	Table 1
I	Architectural Detail Levels/Layers

Level#	Level/Layer Name	Level/Layer Description
Level#	-	
1	A-ANNO-DIMS	Witness/extension lines, dimension arrowheads/dots/slashes, dimension text
3	A-ANNO-NPLT	Construction lines, area calculations, review comments
4	A-ANNO-PATT	Patterning/hatching
6	A-ANNO-SYMB	Reference bubbles, matchlines and breaklines
7	A-ANNO-TEXT	Detail title text, leaderlines/arrowheads and associated text, notes
9	A-DETL-GENF	General features
12	A-DETL-BLCK	Blocking, furring and spacers
15	A-DETL-CABS	Cabinets
16	A-DETL-CALK	Caulking and sealants
17	A-DETL-CEIL	Ceiling materials (no patterning)
24	A-DETL-EXTR	Extrusions and formed shapes
25	A-DETL-EXWL	Exterior wall materials (no patterning)
27	A-DETL-FAST	Fasteners
30	A-DETL-FLOR	Floor materials (no patterning)
31	A-DETL-FLSH	Flashing
33	A-DETL-GLAZ	Glazing
35	A-DETL-GRLS	Grilles and louvers
36	A-DETL-HDWR	Hardware
37	A-DETL-INSL	Insulation (no patterning)
38	A-DETL-ITWL	Interior wall materials (no patterning)
40	A-DETL-MASY	Masonry
44	A-DETL-PIPE	Piping
46	A-DETL-ROOF	Roof materials (no patterning)
49	A-DETL-STRC	Structural features
53	A-DETL-TRIM	Trim

Table 2 Color/Line Width Guidelines				
Color	AutoCAD Color#	MicroStation Color #	Line/Pen Width	
Blue	5	1	0.007 in. (0.18 mm), LW = 0	
Grey	8	9	0.007 in. (0.18 mm), LW = 0	
Red	1	3	0.010 in. (0.25 mm), LW = 1	
Green	3	2	0.010 in. (0.25 mm), LW = 1	
Yellow	2	4	0.014 in. (0.35 mm), LW = 2	
Magenta	6	5	0.014 in. (0.35 mm), LW = 2	
Cyan	4	7	0.020 in. (0.50 mm), LW = 3	
White	7	0	0.028 in. (0.70 mm), LW = 5	




Figure 4. Patterning/hatching added to detail

Table 3 Inch-Pound Text Heights				
Detail Scale	Height at which Notes and Dimensions Should be Placed	Height at which Detail Title Text Should be Placed		
1/32 in. = 1 ft - 0 in.	4 ft	8 ft		
1/16 in. = 1 ft - 0 in.	2 ft	4 ft		
1/8 in. = 1 ft - 0 in.	1 ft	2 ft		
1/4 in. = 1 ft - 0 in.	6 in.	1 ft		
3/8 in. = 1 ft - 0 in.	4 in.	8 in.		
1/2 in. = 1 ft - 0 in.	3 in.	6 in.		
3/4 in. = 1 ft - 0 in.	2 in.	4 in.		
1 in. = 1 ft - 0 in.	1-1/2 in.	3 in.		
1-1/2 in. = 1 ft - 0 in.	1 in.	2 in.		
3 in. = 1 ft - 0 in.	1/2 in.	1 in.		
6 in. = 1 ft - 0 in.	1/4 in.	1/2 in.		
Full Size	1/8 in.	1/4 in.		

Table 4 Metric Text Heights				
Detail Scale	Height at which Notes and Dimensions Should be Placed	Height at which Detail Title Text Should be Placed		
1:200	600 mm	1200 mm		
1:125	375 mm	750 mm		
1:100	300 mm	600 mm		
1:75	225 mm	450 mm		
1:50	150 mm	300 mm		
1:25	75 mm	150 mm		
1:20	60 mm	120 mm		
1:10	30 mm	60 mm		
1:5	15 mm	30 mm		
1:2.5	7.5 mm	15 mm		
Full Size	3 mm	6 mm		




Figure 5. Text, dimensions, leader lines, and titles added to detail





Figure 6. Naming convention. Note: A full listing of *UniFormat* categories and codes is outlined in Chapter 5, "Index of Details"

An example of a detail name is provided below.



3 CADD Detail Manager

Introduction

The CADD Details Library is supplied on a CD-ROM with a menu-driven retrieval system called the CADD Detail Manager (CDM). The CDM allows the user to select border sheets, preview details, and scale details for proper placement into a drawing file.

Details are located within the CDM by selecting a Discipline (e.g., Architectural, Mechanical, etc.), a combination of Level 1 and Level 2 Categories (e.g., Exterior Closure, Roofing, etc.), and the Detail Code (e.g., Exterior Walls, Exterior Windows, etc.). Once all three selections are made, a list of details within the selected code for that discipline will be displayed. Individual details may be previewed by selecting (highlighting) the detail names displayed within the list box. Choosing the appropriate scale and inserting the detail into the current drawing completes the selection/placement process.

Startup

Although the AutoCAD and MicroStation versions of the CDM function similarly, there are minor differences in the way these utilities work. These differences will be discussed in the following sections.

MicroStation Version (95/SE)

The MicroStation version of the CADD Detail Manager was developed using MicroStation Development Language (MDL). To start the CADD Detail Manager, create a new or open an existing design file. In the MicroStation Key-in window, enter the following command:

mdl load detail

When this command is entered, the CADD Detail Manager disclaimer box will open. After the "OK" button is clicked, the CADD Detail Manager Setup box will appear (Figure 7). From this point on, the use of the CADD Detail Manager in either Auto-CAD or MicroStation is the same (see "CADD Detail Manager Setup").



Figure 7. Detail Manager Setup box

AutoCAD Version (Release 13/14)

The AutoCAD version of the CADD Detail Manager was developed using AutoLISP. To start the CADD Detail Manager within AutoCAD, first open a new drawing. At the Command line, the following needs to be typed:

Command: CDM

When this command is entered, the CADD Detail Manager disclaimer box will open. After clicking on the "OK" button, the user will have the choice of either starting a new detail sheet or opening an existing detail sheet (Figure 8).



Figure 8. New or existing sheet option box

Choosing the New option from Figure 8 starts the CADD Detail Manager Setup (Figure 7). From this point, the use of the CADD Detail Manager in either AutoCAD or MicroStation is the same.

Choosing the Existing option will allow the user to search for an existing details sheet using a file manager routine (Figure 9).




Figure 9. Existing details sheet file search

CADD Detail Manager Setup

As shown in Figure 7, the user first has to set the units of the drawing—either inchpound or metric. The user then has the option of selecting an existing border sheet file, one of the metric border sheets included on the CADD Details Manager CD, or no border sheet at all. If an existing border sheet is chosen, that sheet has to have been drawn full size (e.g., an ANSI D size border sheet has to measure 22 in. by 34 in.). Once all desired settings have been chosen, click the "OK" button, which will start the CADD Detail Manager.

Note: In MicroStation, if inch-pound units are chosen, the working units are reset to 1:12:8000 and for metric units, the working units are reset to 1:1:10 (Figure 10). These working units conform to those mandated in Release 1.8 of the Tri-Service A/E/C CADD Standard.



Figure 10. Working units warning box

CADD Detail Manager Use

Within the CADD Detail Manager (Figure 11), details are cataloged first by discipline (i.e., Architectural, Electrical, Mechanical, etc.). Once a discipline is chosen, the user then can select from different UniFormat Level 2 Categories and Detail Codes until a list of details within those selections appears. Each line within the resulting list of details gives three pieces of information: the name of the detail, the detail description, and the insertion scale for that detail. Clicking on a particular detail causes an image of that detail to appear in the Preview box.

Before a desired detail can be inserted, the correct insertion scale for that detail needs to be set (as mentioned previously, the insertion scale is listed along with the detail name and description in the Available Details list box). To set the insertion scale, click the "Scale" button. The user will then be taken to a scale conversion dialog box (Figure 12). From this box, the scale matching that noted in the detail description should be chosen (Note: the user must select

a scale, otherwise the detail will not insert at the proper size). Once the correct scale is chosen, the user will be taken back to the CADD Detail Manager screen (Figure 11), where the "Insert" option should be chosen. The user will then be allowed to drag the detail to the desired position and insert it into the drawing. This detail should then be edited/modified to meet site-specific requirements. Similarly, more details can be inserted into the existing drawing until a complete sheet of details is created.

Other Installation Options

As delivered, the setup routines included with the CADD Details Library CD install configuration files that point to the CD-ROM drive as the location for certain files. It is possible that a site may want these files shared over a server. In order to locate the details files, the installed configuration files need to be edited to point to the new location. In AutoCAD, this file is called cdm_set.dfs and is saved to the AutoCAD "Support" directory. In MicroStation, this




Figure 11. CADD Detail Manager




Figure 12. Scale conversion

file is called ustncfg.dos and is stored in a new directory called "Details" under the

MicroStation directory. Both configuration files contains directory paths similar to the following (in this case, the CD-ROM drive was E:):

E:\DETAILS\SHEETS\ANSID.DGN

C:\win32app\USTN95\DETAILS\SETUP.UNI

E:\DETAILS\INDEX\

E:\DETAILS\USTN\

If the files contained within the directory "Details" on the CD are copied to a server or another location, then the path to those files needs to be changed appropriately.

4 Design/Construction Field Working Group

The Design/Construction Field Working Group (FWG) is composed of architects, interior designers, and engineers from various design agencies within the Army, Navy, Air Force, and Corps of Engineers. The Design/Construction FWG's primary function is to serve as a leader in the improved usage of CADD technology as it relates to the design disciplines. The group reviews and reports

on the status of CADD within the triservices, recommends and/or prepares standards, and implements productivity enhancements within DoD.

Table 5 lists current Design/Construction FWG members.

Table 5 Design/Construction Field Working Group				
Member	Site	Service		
Brenda Langheld	Brooks AFB	Air Force		
James Roesch	Grand Forks AFB	Air Force		
Larry Strother	Tyndall AFB	Air Force		
Sharrol Toenjes	Scott AFB	Air Force		
David Gutierrez	Fort Sam Houston	Army		
Mike Luhrman	Fort Sam Houston	Army		
Alex Shum	Fort Sam Houston	Army		
Robert Weaver	Fort Carson	Army		
Richard Allwes	Pittsburgh District	Corps		
Lisa Edwards	Huntington District	Corps		
Ghassem Khosrownia	Sacramento District	Corps		
Stan Shirk	Omaha District	Corps		
Marsha Walkup	Kansas City District	Corps		
Gary Boyd	Southern Division	Navy		
James Gale	Atlantic Division	Navy		
Edward Ruckle	Southwest Division	Navy		

5 Index of Details

Note:	"*" = .dgn/.dwg	A202	Basement Walls
	"**" = metric version of detail	A2020	Misc. Basement Wall Details
	available	A2021	Basement Wall Construction
		A2022	Basement Wall Vertical
A SUB	STRUCTURE		Waterproofing
		A2023	Basement Wall Dampproofing
A10	FOUNDATIONS	A2024	Basement Wall Vapor Retarders
A101	Standard Foundations		and Insulation
A1010	Misc. Standard Foundation Details	A2025	Basement Wall Interior Skin
A1011	Wall Foundations		
A1012	Column Foundations	B SHE	LL
A102	Special Foundations	B10	SUPERSTRUCTURE
	Misc. Special Foundation Details	B101	
	Driven Piles	B1010	Misc. Floor Construction Details
A1022	Bored/Augured Piles	B1011	Floor Structural Frame
	Shoring and Underpinning		Structural Interior Walls Supporting
	Dewatering		Floors
	Raft Foundations	B1013	Floor Decks, Slabs and Sheathing
A1026	Cofferdams		Balcony Floor Construction
		B1015	Mezzanine Construction
A103	Slabs on Grade	B1016	Ramps
A1030	Misc. Slab on Grade Details	B1017	Floor Construction Vapor Retarders
A1031	Standard Slabs on Grade		Air Barriers, and Insulation
A1032	Structural Slabs on Grade	B1018	Floor Construction Fireproofing
A1033	Inclined Slabs on Grade	B1019	Floor Construction Firestopping
A1034	Trenches		
A1035	Pits and Bases	B102	Roof Construction
A1036	Subdrainage Systems	B1020	Misc. Roof Construction Details
A1037	Perimeter Insulation	B1021	Roof Structural Frame
		B1022	Structural Interior Walls Supporting
	BASEMENT CONSTRUCTION		Roofs
	Basement Excavation	B1023	Roof Decks, Slabs, and Sheathing
	Misc. Basement Excavation Details		Canopies
A2011	Excavation for Basement	B1025	Roof Construction Vapor Retarders,
A2012	Backfill and Compaction		Air Barriers, and Insulation

A2013 Excavation Support Systems

B1026	Roof Construction Fireproofing	**B20	1616X.* - Louver Jamb
B1027	Roof Construction Firestopping	B20	1617X.* - Head Detail
		**B20	1618X.* - Louver Sill
B103	Typical Structural Details	B20	1619X.* - Jamb Detail
B1030	Misc. Details	B20	1620X.* - Sill Detail
B1031	Steel Details	B2017	Exterior Protection Devices
B1032	Concrete Details		for Openings
B1033	CMU Details	B20	1701X.* - Pipe Guard Detail
B1034	Timber Details	B2018	Exterior Balcony Walls and
			Railings
B20	EXTERIOR CLOSURE	B2019	Exterior Soffits
B201	Exterior Walls		
B2010	Misc. Exterior Wall Details	B202	Exterior Windows
**B20	1001X.* - Sealant Joint	B2020	Misc. Exterior Window Details
B20	01002X.* - (Omitted)	B20	2001X.* - Aluminum Window Jamb Detail
B20	01003X.* - Wall Detail	**B20	2002X.* - Head Detail
B20	01004X.* - Wall Panel Expansion Joint Detail	B20	2003X.* - Jamb Detail
	01005X.* - Wall Detail	**B20	2004X.* - Head Detail
B20	01006X.* - (Omitted)	**B20	2005X.* - Head/Jamb Detail
**B20	1007X.* - Sealant Joint	B20	2006X.* - Head Detail
**B20	1008X.* - Sealant Joint	**B20	2007X.* - Jamb Detail
**B20	1009X.* - Sealant Joint	**B20	2008X.* - Jamb Detail
**B20	1010X.* - Sealant Joint	B20	2009X.* - Head Detail
**B20	1011X.* - Sealant Joint	B20	2010X.* - Jamb Detail
**B20	1012X.* - Sealant Joint	**B20	2011X.* - Sill Detail
**B20	1013X.* - Sealant Joint	**B20	2012X.* - Sill Detail
B2011	Exterior Wall Exterior Skin/Interior	B20	2013X.* - Head/Sill Detail
	Skin	B20	2014X.* - Sill Detail
B20	01101X.* - Metal Stud Partition	B20	2015X.* - Sill Detail
B2012	Exterior Wall Construction	**B20	2016X.* - Sill Detail
B2013	Exterior Wall Vapor Retarders, Air	B20	2017X.* - Sill Detail
	Barriers, and Insulation	**B20	2018X.* - Jamb Detail
B2014	Exterior Wall Assemblies	B20	2019X.* - Head Detail
B2015	Parapets	**B20	2020X.* - Sill Detail
	Exterior Louvers, Grilles,	B20	2021X.* - Window Sill Detail
	and Screens	**B20	2022X.* - Jamb Detail
**B20	1601X.* - Louver Head	**B20	2023X.* - Window Head Detail
B20	01602X.* - Louver Detail (Head/Jamb)	**B20	2024X.* - Window Sill Detail
**B20	1604X.* - Louver Jamb	B20	2025X.* - Aluminum Window Detail
B20	01605X.* - Louver Detail (Sill)	**B20	2026X.* - Head Detail
**B20	1606X.* - Head Detail	**B20	2027X.* - Sill Detail
**B20	1607X.* - Louver Jamb	**B20	2028X.* - Window Jamb Detail
**B20	1608X.* - Louver Sill	B2021	Exterior Standard Windows
B20	01609X.* - Head (Louver) Detail	B2022	Storefronts
**B20	1610X.* - Louver Sill	B2023	Glazed Curtain Walls
)1611X.* - Head Detail	B2024	Exterior Special Windows
B20	01612X.* - Sill (Louver) Detail		-
	01613X.* - Louver Head	B203	Exterior Doors
B20	01614X.* - Head Detail/Jamb/Sill	B2030	Misc. Exterior Door Details
B20	01615X.* - Head Detail	**B20	3001X.* - Head Detail

Chapter 5 Index of Details 15

B203002X.* - Head Detail **B203052X.* - Sealant Joint B203003X.* - Head Detail **B203053X.* - Sealant Joint **B203004X.* - Head Section **B203054X.* - Sealant Joint **B203005X.* - Jamb Detail B203055X.* - Sill Detail B203006X .* - Jamb Detail B203056X.* - Sill Detail B2031 Exterior Entrance Doors B203007X.* - Jamb Detail **B203008X.* - Head Detail B2032 Exterior Utility Doors B203201X.* - Hanger Door Head Detail B203009X.* - Head Detail **B203202X.* - Pilot Door Head Detail **B203010X.* - Head Detail B203011X.* - (Omitted) (Jamb Sim.) **B203012X.* - Jamb Detail **B203203X.* - Semi-Recessed F.E.C. Head Detail **B203013X.* - Head Detail B203204X.* - Hanger Door Meeting Edge B203014X.* - Head Detail B203205X.* - Hanger Door Weatherseal B203015X.* - Head Detail B203206X.* - Pilot Door Sill Detail **B203016X.* - Jamb Detail B203207X.* - Semi-Recessed F.E.C. **B203017X.* - Head Detail B203208X.* - Hanger Door Jamb Detail **B203018X.* - Head Detail B203209X.* - Hanger Door Jamb Detail Above B203019X.* - Head/Jamb Detail CMU Wainscot B203020X.* - (Omitted) B203210X.* - Jamb Detail B203021X.* - Head Detail B203211X.* - Vertical Lift Door Head **B203022X.* - Jamb Detail B203212X.* - Vertical Lift Door Head B203023X.* - Head Detail B203213X.* - Sill Detail **B203024X.* - Jamb Detail B203214X.* - Jamb Detail B203215X.* - Vertical Lift Door Head B203025X.* - (Omitted) **B203026X.* - Head Detail **B203216X.* - Door Jamb **B203027X.* - Head Detail **B203217X.* - Head Detail **B203028X.* - Head/Jamb Detail **B203218X.* - Door Sill **B203029X.* - Head/Jamb Detail **B203219X.* - Door Head **B203030X.* - Jamb Detail B203220X.* - Sill Detail B203031X.* - Jamb Detail **B203221X.* - Door Jamb **B203032X.* - Sill Detail **B203222X.* - Sill Detail **B203033X.* - Sill Detail **B203223X.* - Jamb Detail **B203034X.* - Sill Detail **B203224X.* - Head Detail B203035X.* - Sill Detail B203225X.* - Sill Detail B203036X.* - Sill Detail B203226X.* - Sill Detail B203037X.* - Sill Detail **B203227X.* - Jamb Detail **B203228X.* - Sill Detail B203038X.* - Sill Detail **B203229X.* - Jamb Detail **B203039X.* - Sill Detail B203040X.* - Sill Detail **B203230X.* - Head Detail **B203231X.* - Sill Detail B203041X.* - Sill Detail B203042X.* - Sill Detail B2033 Large Exterior Special Doors B2034 Special Use Exterior Doors B203043X.* - Sill Detail B2035 Exterior Gates B203044X.* - Sill Detail **B203045X.* - Threshold Detail **ROOFING B30 B203046X.* - Jamb Detail **Roof Coverings** B203047X.* - (Omitted) B3010 Misc. Roof Covering Details B203048X.* - Sill Detail **B203049X.* - Sill Detail **B301002X.* - Lightning Protection - Air **B203050X.* - Sill Detail

B203051X.* - Sill Detail

B301003X.* - Detail at Roof Access Door

B301004X.* - Curb Detail B301053X.* - Eave Detail B301005X.* - Roof Relief Joint Detail B301054X.* - Curb Detail **B301006X.* - Roof Scuttle B3011 Deck Vapor Retarders and **B301007X.* - Roof Drain Details Insulation B3012 Shingles and Roofing Tiles B301008X.* - (Omitted) **B301009X.* - Plumbing Vent Detail B3013 Manufactured Roofing B3014 Membrane Roofing **B301010X.* - Roof Detail **B301011X.* - Roof Detail **B3015 Traffic Coatings B3016 Sheet Metal Roofing **B301012X.* - Conductor Head Detail **B301013X.* - Roof Detail B3017 Flashing and Sheet Metal B3018 Roof Specialties and Accessories **B301014X.* - Rake Detail **B3019** Manufactured Exterior Specialties B301015X.* - Rake Detail **B301016X.* - Gable Rake Detail **B302** Roof Openings **B301017X.* - Roof Vent Detail B3020 Misc. Roof Opening Details B301018X.* - Rake Detail B3021 Skylights B301019X.* - (Omitted) B301020X.* - Metal Ridge Cover Detail B301021X.* - Roof Ridge Detail **CINTERIORS** B301022X.* - Roof Edge Detail C10 INTERIOR CONSTRUCTION B301023X.* - Rake Detail C101 **Interior Partitions** B301024I.* - Downspout Strap Detail C1010 Misc. Interior Partition Details **B301025X.* - Eave Detail C101001X.* - Door Pocket B301026X.* - Roof Edge Detail B301027X.* - Boiler Stack Detail C101002X.* - (Omitted) B301028X.* - Expansion Joint Detail C101003X.* - Elevation at Joist Pocket C101004X.* - Wall Detail at Joist Pocket B301029X.* - Lightning Protection - Air Termina1 C101005X.* - Head Detail B301030X.* - Roof Edge Detail C101006X.* - Wall Latch Detail B301031X.* - Rake Detail C101007X.* - CMU Partition Bracing Detail B301032X.* - Plumbing Vent Detail C101008X.* - Partition Wall Bracing B301033X.* - Roof Detail C101009X.* - Caging Detail B301034X.* - Fascia Detail C101010X.* - Caging Detail B301035I.* - Snowguard Detail C101011X.* - Caging Door Detail B301036X.* - Furnace Flue Detail C101012X.* - Caging Door Detail B301037X.* - Expansion Joint C101013X.* - Caging Door Detail B301038X .* - Edge Detail C101014X.* - Caging Door Detail B301039X.* - Vent Stack C101015X.* - Wire Mesh Detail C101016E.* - Wire Mesh Detail B301040X.* - Expansion Joint B301041X.* - Seam Lap Detail C101017X.* - Wire Mesh Detail C101018X.* - Wire Mesh Door Jamb Detail B301042X.* - Gutter Detail B301043X.* - Curb Flashing C101019X.* - Wire Mesh Detail B301044X.* - Roof Edge Detail C101020X.* - Wire Mesh Shelving B301045X.* - Roof Edge Detail C101021X.* - Expansion Joint Detail C101022X.* - Expansion Joint Detail B301046X.* - Ridge Detail B301047X.* - Rake Detail C101023X.* - Fire Rated Gypsum Detail B301048X.* - Valley Detail C101024X.* - Typical Expansion Joint B301049X.* - Fascia Detail C101025X.* - Fire Rated Column Detail B301050X.* - Rake/Gable Detail C101026X.* - Fire Rated Column Detail C101027X.* - Wall Detail B301051X.* - Downspout Detail (Typ.) C101028X.* - Fire Rated Wall Detail B301052X.* - Curb Detail

Chapter 5 Index of Details 17

C101029X.* - Gypsum Wall Detail C101064X.* - Jamb Detail C101030X.* - Gypsum Wall Detail C101065X.* - Sill Detail C101031X.* - Jamb Detail C101066X.* - Sill Detail C101067X.* - Sill Detail C101032X.* - Gypsum Wall Detail C101033X.* - Gypsum Wall Detail C101068X.* - Service Window Sill Detail C101034X.* - (Omitted) (Block Wall) C101035X.* - Concrete Masonry Unit C101069X.* - Service Window Section (GWB One Side) w/Counter C101070X.* - Service Window Section C101036X.* - Concrete Masonry Unit (GWB Each Side) C101071X.* - (Omitted) C101037X.* - Concrete Masonry Unit (Cer. C101072X.* - Jamb Detail C101073X.* - Head Detail Tile One Side) C101038X.* - Concrete Masonry Unit (Cer. C101074X.* - Jamb Detail Tile One Side) C101075X.* - Jamb Detail C101039X.* - (Omitted) C101076X.* - (Omitted) C101040X.* - Plumbing Chase (Pre-Glazed C101077X.* - Jamb Detail One Side) C101078X.* - Wall Type Detail C101079X.* - Wall Type Detail C101041X.* - (Omitted) C101042X.* - (Omitted) C101080X.* - Wall Type Detail C101043X.* - Metal Stud Partition (GWB C101081X.* - Wall Type Detail C101082X.* - Wall Type Detail (1 Hr. One Side) C101044X.* - Metal Stud Partition (GWB Fire Rated) Each Side) C101083X.* - Wall Type Detail (1 Hr. C101045X.* - Metal Stud Partition (Cer. Fire Rated) Tile/GWB) C101084X.* - Wall Type Detail (1 Hr. C101046X.* - Metal Stud Partition (GWB/GRC Fire Rated) C101085X.* - (Omitted) C101047X.* - Metal Stud Partition (Cer. C101086X.* - Wall Type Detail (1 Hr. Tile One Side) C101048X.* - Metal Stud Partition (Cer. C101087X.* - Wall Type Detail (1 Hr. Fire Rated) Tile Each Side) C101049X.* - Plumbing Chase (Cer. Tile C101088X.* - Wall Type Detail C101089X.* - Wall Type Detail Room Side) C101090X.* - Wall Type Detail C101050X.* - Metal Stud Partition (GWB Each Side) C101091X.* - Wall Type Detail C101051X.* - Metal Stud Partition (Cer. C101092X.* - Wall Type Detail C101093X.* - Wall Type Detail (1 Hr. Tile/GWB) Fire Rated) C101052X.* - Existing CMU (GWB Each Side) C101053X.* - Existing CMU (GWB Each Side) C1011 Interior Fixed Partitions C1012 Interior Demountable Partitions C101054X.* - Existing CMU (GWB/Metal Wall) C1013 Interior Operable Partitions C101055X.* - Plumbing Chase (Cer. Tile C1014 Interior Balustrades and Screens One Side) C1015 Interior Windows C101056X.* - Head Detail C1016 Interior Glazed Partitions and C101057X.* - Head Detail Storefront C101058X.* - Head Detail C1017 Interior Partition Firestopping C101059X.* - Head/Sill Detail C101060X * - Head Detail C102 Interior Doors C101061X.* - Jamb Detail C1020 Misc. Interior Door Details C101062X.* - Jamb Detail

C101063X.* - Jamb Detail

C10	2001X.* - Head Detail	C103001X.* - Door Elevation at Hoist Beam	
C10	2002X.* - Head Detail	C103002X.* - Hoist Beam Penetration Detail	
C10	2003X.* - Jamb Detail	C103003X.* - Head Detail	
C10	2004X.* - Jamb Detail	C103004X.* - Jamb Detail	
C10	2005X.* - Jamb Detail	C103005X.* - Sill Detail	
C10	2006X.* - Head Detail	C103006X.* - Head Detail	
C10	2007X.* - Head Detail	C103007X.* - (Omitted)	
C10	2008X.* - Head Detail	C1031 Visual Display Boards, Telephones	•
C10	22009X.* - Jamb Detail	Identifying Devices, and Postal	
C10	22010X.* - Jamb Detail	Specialties	
C10	02011X.* - Jamb Detail	C103101E.* - Bulletin Board Detail	
C10	2012X.* - Head Detail	C103101X.* - Bulletin Board Section	
C10	2013X.* - Jamb Detail	C103102X.* - Telephone Cabinet Detail	
C10	2014X.* - Head Detail	C103103X.* - Marker Board Detail	
C10	02015X.* - (Omitted)	C1032 Compartments and Cubicles	
C10	2016X * - Head Detail	C103201X.* - Toilet Partition Hanger Detail	
C10	2017X.* - Head Detail	C103202X.* - Shower Detail	
C10	2018X.* - Jamb Detail	C103203X.* - Shower Wall Detail	
C10	2019X.* - Sill Detail	C1033 Interior Louvers and Vents	
C10	02020X.* - (Omitted)	C1034 Service Wall Systems and Wall and	Ĺ
C10	2021X.* - Sill Detail	Corner Guards	
C10	2022X.* - Sill Detail	C1035 Fireplaces and Stoves	
C10	2023X.* - Sill Detail	C1036 Pedestrian Control Devices	
C10	2024X.* - Sill Detail	C1037 Lockers, Wardrobes, Closet,	
C10	2025X.* - Sill Detail	Storage, and Shelving Specialties	
C10	02026X.* - (Omitted)	C1038 Toilet and Bath Accessories (Scales	s)
C10	02027X.* - Sill Detail	C103801X.* - Mirror Details	
C10	02028X.* - (Omitted)		
C10	2029X.* - Sill Detail	C20 STAIRWAYS	
C10	22030X.* - (Omitted)	C201 Stair Construction	
C10	22031X.* - Sill Detail	C2010 Misc. Stair Construction Details	
C10	22032X.* - (Omitted)	C201001E.* - Fixed Ladder Elevation	
C10)2033X.* - (Omitted)	C201001X.* - Metal Stair Landing Detail	
C10	22034X.* - Sill Detail	C201002X.* - Metal Stair Tread Detail	
)2035X.* - (Omitted)	C201003X.* - Stair Landing Detail	
C10	2036X.* - Head Detail	C201004X.* - Stair Detail	
C10)2037X.* - (Omitted)	C201005X.* - Stair Detail	
	2038X.* - Head Detail	C2011 Cast-in-Place Stair Construction	
	2039X.* - Head Detail	C2012 Precast Concrete Stair Construction	1
	02040X.* - (Omitted)	C201201X.* - Stair Detail	
	Interior Swinging Doors	C201202X.* - Stair Detail	
	Interior Entrance Doors	C201203X.* - Bottom Stair Detail	
	Interior Fire Rated Doors	C2013 Metal Stair Construction	
	Interior Sliding and Folding Doors	C201301E.* - Top Metal Stair Detail	
	Interior Large Doors	C201302E.* - Bottom Metal Stair Detail	
	Interior Special Use Doors	C201302X.* - Landing Detail	
C1027	Interior Gates	C201303E.* - Metal Stair Detail	
~4.0.5		C201303X.* - Metal Stair Detail	
C103	Interior Specialties	C201304X.* - Top Metal Stair w/Square Tube	
C1030	Misc. Interior Specialty Details	Posts and Rails	

Chapter 5 Index of Details 19

C20	1305X.* - Metal Stair Detail	C302007X.* - Sealant Joint
C20	1306X.* - Landing Detail	C302008X.* - (Omitted)
C20	1307X.* - Landing Detail	C3021 Concrete Floor Finishes
C20	1308X.* - Landing Detail	C3022 Tile Floor Finishes
C20	1309X.* - Landing Detail	C3023 Terrazzo Floor Finishes
C20	1310X.* - Metal Stair Detail	C3024 Wood Flooring
C20	1311X.* - Landing Detail	C3025 Stone Flooring
C20	1312X.* - Tread Detail	C3026 Unit Masonry Flooring
C2014	Wood Stair Construction	C3027 Resilient Flooring
C2015	Fire Escapes	C3028 Carpet Flooring
		C3029 Access and Special Flooring, Floor
C202	Stair Finishes	Treatment, and Floor Painting
C2020	Misc. Stair Finish Details	C302901X.* - Ramp Detail
C2021	Tile Stair Finishes	C302902X.* - Raised Floor Detail
C2022	Terrazzo Stair Finishes	C302903X.* - Raised Floor Detail
C2023	Stone Stair Finishes	C302904X.* - Raised Floor Acoustical Wall
C2024	Unit Masonry Stair Finishes	Detail
C2025	Resilient Stair Finishes	
C2026	Carpet Stair Finishes	C303 Interior Ceiling Finishes
C2027	Special Flooring Stair Finishes	C3030 Misc. Interior Ceiling Finish
C2028	Stair Treatment/Painting	Details
C2029	Stair Railings/Soffits	C303001X.* - Lay-In Ceiling Detail
C20	2901X.* - Handrail Mounting Detail	C303002X.* - Lay-In Ceiling Detail
		C303003X.* - Lay-In Ceiling Detail
C30	INTERIOR FINISHES	C303004X.* - Lay-In Ceiling Detail
C301	Interior Wall Finishes	C303005X.* - Lay-In Ceiling Detail
C3010	Misc. Wall Finish Details	C303006X.* - Lay-In Ceiling Detail
	Concrete Wall Finishes	C303007X.* - Plaster Ceilings Detail
	Wood Wall Paneling	C303008X.* - Plaster Ceilings Detail
	Lath and Plaster Wall Finishes	C303009X.* - Lay-In Ceiling Detail
	Gypsum Board Wall Finishes	C303010X.* - Lay-In Ceiling Detail
	Tile and Terrazzo Wall Finishes	C303011X.* - Gypsum Ceiling Detail
C3016	Stone Facing and Acoustical Wall	C303012X.* - Plaster Ceiling Detail
	Finishes	C303013X.* - Plaster Ceiling Detail
	Special Wall Finishes	C303014X.* - Lay-In Ceiling Detail
	Wall Carpet	C303015X.* - Lay-In Ceiling Detail
C3019	Interior Wall Painting, Wall	C303016X.* - Plaster Ceiling Detail
	Coverings, and Special Interior	C303017X.* - Ceiling Access Panel
	Wall Coatings	C303018X.* - Plaster Ceiling Detail
		C303019X.* - Ceiling Control Joint Details
C302	Interior Floor Finishes	C3031 Concrete Ceiling Finishes
	Misc. Floor Finish Details	C3032 Wood Ceiling Paneling
	2001X.* - Base Detail	C3033 Lath and Plaster Ceiling Finishes
	2002X.* - Expansion Joint Detail	C3034 Gypsum Board Ceiling Finishes
	2003X.* - Expansion Joint Detail	C3035 Acoustical Ceiling Treatment
	2004X.* - Expansion Joint Detail	C3036 Special Ceiling Surfaces
	2005X.* - Expansion Joint Detail	C3037 Special Ceiling Coatings
C30	2006X.* - Sealant Joint	C3038 Interior Ceiling Painting

20

D SER	VICES	D203	Sanitary Waste Systems
		D2030	Misc. Details
D10	CONVEYING SYSTEMS	D2031	Waste and Vent Piping Systems
D101	Vertical Transportation Systems	D2032	Waste Piping Specialties
D1010	Misc. Details	D2033	Waste Piping Equipment
D1011	Dumbwaiters	D2034	Waste Piping Insulation
D1012	Elevators	D2035	Acid Waste Systems
D1013	Escalators		•
D1014	Lifts	D204	Rain Water Drainage Systems
		D2040	Misc. Details
D102	Other Transportation Systems	D2041	Rain Water Drainage Piping
D1020	Misc. Details		Systems
D1021	Moving Walks	D2042	Rain Water Drainage Specialties
D1022	Aircraft Passenger Loading Systems	D2043	Rain Water Drainage Insulation
	•	D205	Special Plumbing Systems
D103	Other Conveying Systems		Misc. Special Plumbing Details
	Misc. Conveying Details		Medical Gas Systems
	Material Handling Systems		Helium Gas Systems
	Bridgecranes		Liquid Oxygen Systems
	Monorails		Vacuum Systems
	Jib Cranes		Natural Gas Systems
	Misc. Hoists		Liquified Petroleum Gas Systems
	Turntables		Deionized/Distilled Water Systems
	Scaffolding		Reverse Osmosis Systems
	Special Crane Supports		Fountain Equipment and Piping
D20	PLUMBING SYSTEMS	D206	Compressed Air Systems
D201	Plumbing Fixtures	D2060	Misc. Compressed Air Details
	Misc. Plumbing Fixture Details Water Closets	D2061	Compressed Air Piping and Equipment
	Urinals	D2062	Compressed Air Legends and
	Lavatories	D2002	Schematics
D2013			Seliciliaties
	Showers	D30	HEATING, VENTILATING, AND
	Bathtubs	250	AIR CONDITIONING (HVAC)
	Basins		SYSTEMS
	Drinking Fountains/Coolers	D301	Fuel Supply Systems
	Other Plumbing Fixture Details		Misc. Fuel Supply Details
D2017	Other Framonig Fixture Details		Oil Supply Systems
D202	Domestic Water Distribution		Gas Supply Systems
	Misc. Details		Coal Supply Systems
	Water Supply Piping Systems	D 3013	Cour Supply Systems
	Water Supply Plumbing Specialties	D302	Heat Generation Systems
	Water Supply Fullioning Speciatries Water Supply Equipment		Misc. Heat Generation Details
	Water Supply Insulation		Steam Boilers
	Electric Water Heater		Hot Water Boilers
	Gas Fired Water Heater		Furnaces
~~~~	11 VW 11 W VVI 11 VW VVI	- 20-2	

Chapter 5 Index of Details 21

	Fuel-Fired Heaters Auxiliary Equipment	D3073	Air Systems Testing, Adjusting, and Balancing
	Heat Rejection Systems	D308	Special HVAC Systems and
	Misc. Heat Rejection Details		Equipment
	Absorption Chillers		Misc. Details
	Centrifugal Chillers	D3081	Solar Energy Collection,
	Reciprocating Chillers		Conversion, and Storage
	Rotary-Screw Chillers	D3082	Industrial Ventilation
	Cooling Towers and Liquid Coolers		
D3036	Refrigerant Compressors and	<b>D40</b>	FIRE PROTECTION SYSTEMS
	Condensers	D401	Fire Protection Sprinkler Systems
D3037	Heat Pumps		Misc. Sprinkler Details
			Wet Pipe Sprinkler Systems
	Heat Distribution Systems		Dry Pipe Sprinkler Systems
	Misc. Heat Distribution Details		Pre-Action Sprinkler Systems
	Air Distribution Systems	D4014	Combination Dry Pipe and
	Steam Distribution Systems		Pre-Action Sprinkler Systems
	Hydronic Distribution Systems		Deluge Sprinkler Systems
D3044	Exhaust and Ventilation Systems	D4016	Fire Pumps
	Heat Transfer	D402	Standpipe and Hose Systems
	Misc. Heat Transfer Details		Misc. Standpipe Details
	Heat Exchangers		Fire Protection Standpipe
D3052	Package Terminal Air Conditioning Systems(PTAC)	D4022	Fire Protection Valves, Hoses, and Cabinets
D3053	Split Systems		
D3054	Air Coils	<b>D403</b>	Fire Protection Specialties
D3055	Humidifiers	D4030	Misc. Specialty Details
D3056	Dehumidifiers	D40	3001X.* - Fire Entinguisher Cabinet Detail
D3057	Terminal Heat Transfer Units	D40	3002X.* - Fire Entinguisher Cabinet Detail
D3058	Energy Recovery Units		3003X.* - Fire Extinguisher Cabinet Detail 3004X.* - Fire Extinguisher Cabinet
D306	<b>HVAC Controls and</b>		Elevation/Detail
	Instrumentation	D40	3005X.* - Fire Extinguisher Cabinet Section
D3060	Misc. HVAC Control Details	D40	3006X.* - Fire Extinguisher Cabinet Section
D3061	Building Systems Control	D4031	Fire Extinguishers, Cabinets, and
D3062	Energy Management and		Accessories
	Conservation Systems	D4032	Fire Blankets and Cabinets
D3063	HVAC Control Systems	D4033	Wheeled Fire Extinguisher Units
D3064	HVAC Sequence of Operation		
D3065	Gas Purging Systems	<b>D404</b>	<b>Special Fire Protection Systems</b>
		D4040	Misc. Special System Details
<b>D307</b>	HVAC System Testing, Adjusting,	D4041	Foam Extinguishing Systems
	and Balancing		(AFFF)
D3070	Misc. Details	D4042	Carbon Dioxide Extinguishing
D3071	Mechanical Systems Testing,		Systems
	Adjusting, and Balancing	D4043	Halogen Agent Extinguishing
D3072	Piping Systems Testing, Adjusting, and Balancing		Systems

22

D4044	Dry Chemical Extinguishing	D5051	Electrical Systems Controls
	Systems	D5052	Lighting Control Systems
		D5053	Instrumentation
<b>D50</b>	ELECTRICAL SYSTEMS		
D501	Electrical Service and	<b>D506</b>	<b>Electrical Testing</b>
	Distribution	D5060	Misc. Details
D5010	Misc. Details	D5061	Electrical Systems Testing
D5011	Main Transformers		
D5012	Secondary Transformers	<b>D60</b>	SPECIAL MECHANICAL
D5013	Main Switchboards		SYSTEMS
D5014	Interior Distribution Transformers	D601	Fuels and Lubricants
D5015	Branch Circuit Panelboards	D6010	Misc. Fuels and Lubricant Details
D5016	Enclosed Circuit Breakers	D6011	Fuel Oil Systems
D5017	Motor Control Centers	D6012	Fuel Dispensing and Vapor
D5018	Aerial Distribution Details		Recovery
D5019	Underground Distribution Details	D6013	Lubrication Oil Systems
	C		Fuel Storage Tanks
<b>D502</b>	Lighting and Branch Wiring		Day Tanks
	Misc. Lighting and Branch		•
	Wiring Details	D602	Auxiliary/Emergency Power
D5021	Electrical Branch Wiring	D6020	Misc. Details
	Interior Lighting	D6021	Generator Sets
	Exterior Lighting	D6022	Mufflers/Silencers
D503	Communication and Security	D603	Supports
	Systems		Misc. Piping Supports
D5030	Misc. System Details		MSS Piping Supports
D5031	Alarm and Detection Systems	D6032	Seismic Supports
D5032	Clock and Programs Systems	D6033	Fire Suppression Supports
	Voice and Data Systems		
	Public Address and Music Systems	D604	Valves
	Television Systems	D6040	Misc. Valve Details
	Underground Communications		
	Details	D605	Hydropower, Locks, and Dams
			Misc. Civil Works
D504	Special Electrical Systems	D6051	Hydropower Equipment
D5040	Misc. Special System Details		Locks and Dams
D5041	Uninterruptible Power Supply		
	Systems	E EQU	UIPMENT AND FURNISHINGS
D5042	Packaged Engine Generator	_	
	Systems	E10	EQUIPMENT
D5043	Battery Power Systems	E101	Commercial Equipment
D5044	Cathodic Protection	E1010	Misc. Commercial Equipment
D5045	Electromagnetic Shielding Systems		Security and Vault Equipment
	Lightning Protection Systems		Teller and Service Equipment
	Unit Power Conditioners		Registration Equipment
	Grounding Details		Checkroom Equipment
	<u> </u>		Mercantile Equipment
D505	<b>Electrical Controls</b>		Commercial Laundry and Dry
D5050	Misc. Control Details		Cleaning Equipment

Chapter 5 Index of Details 23

Vending Equipment	E20	01012X.* - (Omitted)
		01013E.* - Lavatory Cabinet
office Equipment		01014E.* - Lavatory Cabinet
Institutional Fauinment		01015E.* - Lavatory Cabinet
		01016E.* - Lavatory Cabinet
		01017E.* - Lavatory Capinet 01017E.* - Kitchen/Break Room Counter
* *		
		01018E.* - Lavatory Cabinet
		01019E.* - Kitchen/Break Room Counter
		01020E.* - Lavatory Cabinet
* *		01021E.* - Shelf Detail 01022X.* - Chair Rail Detail
* *		
		01023X.* - Wood Nailer
		01024X.* - Wood Seats (Wall Mounted)
Mortuary Equipment		01025X.* - Wood Base and Chair Rail Detail
<b>X</b> 7.1.1. <b>D</b>		01026X.* - Half Height Wall Cap Detail
		01027E.* - Shelf Detail
1 1		Fixed Artwork
		Fixed Casework
		Window Treatment
		Fixed Floor Grilles and Mats
		Fixed Multiple Seating
Loading Dock Equipment	E2016	Fixed Interior Landscaping
Other Equipment	E202	Movable Furnishings
Maintenance Equipment	E2020	Misc. Movable Furnishings
Solid Waste Handing Equipment	E2021	Movable Artwork
Food Service Equipment	E2022	Furniture and Accessories
Residential Equipment	E2023	Movable Rugs and Mats
Unit Kitchens	E2024	Movable Multiple Seating
Darkroom Equipment	E2025	Movable Interior Landscaping
Athletic, Recreational, and		
Therapeutic Equipment	F OTH	IER BUILDING CONSTRUCTION
•	F10	SPECIAL CONSTRUCTION
* *	F101	Special Structures
		Misc. Special Structures
FURNISHINGS		•
		Pre-Engineered Structures
<u> </u>		E
<u>c</u>	F102	<b>Integrated Construction</b>
		Misc. Integrated Construction
	11020	Details
	F1021	Integrated Assemblies
		Special Purposed Rooms
	11022	Special Larpoota Rooms
	F103	<b>Special Construction Systems</b>
		Misc. Special Construction Systems
	11050	Details
10101 * - Hasp Detail		_ Cours
	Maintenance Equipment Solid Waste Handing Equipment Food Service Equipment Residential Equipment Unit Kitchens Darkroom Equipment Athletic, Recreational, and Therapeutic Equipment Planetarium/Observatory Equipment Agricultural Equipment  FURNISHINGS Fixed Furnishings Misc. Fixed Furnishings 1001X.* - Reception Counter Detail 1002X.* - Sink Detail 1003X.* - Base Cabinet Detail 1004X.* - (Omitted) 1005X.* - (Omitted) 1007X.* - (Omitted) 1007X.* - (Omitted) 1008X.* - (Omitted) 1008X.* - (Omitted) 1008X.* - (Omitted)	Institutional Equipment

E201011X.* - (Omitted)

F1031	Sound, Vibration, and Seismic Construction	G1042	Excavating, Backfilling, and Compacting
F1032	Radiation Protection	G1043	Soil Stabilization
F1033	Special Security Systems	G1044	Slope Protection and Erosion Control
F104	Special Facilities	G1045	Earth Dams
F1040	Misc. Special Facility Details		
F1041	Aquatic Facilities	G105	Hazardous Waste Removal
F1042	Ice Rinks		
F1043	Site Constructed Incinerators	<b>G20</b>	SITE IMPROVEMENTS
F1044	Kennels and Animal Shelters	G201	Roadways
F1045	Liquid and Gas Storage Tanks	G2011	Roadway Base Courses
		G2012	Flexible Roadway Pavement
F105	Special Controls and		Roadway Unit Pavers
	Instrumentation		Rigid Roadway Paving
F1050	Misc. Special Controls and		Roadway Curb and Gutter
	Instrumentation Details	G2016	Roadway Appurtenances
	Recording Instrumentation		
	Building Automation Systems		Parking Lots
F1053	Fire Suppression and Supervisory		Parking Lot Base Courses
	Systems		Flexible Parking Lot Pavement
			Parking Lot Unit Pavers
F20	SELECTIVE DEMOLITION		Rigid Parking Lot Paving
F201	<b>Building Elements Demolition</b>		Parking Lot Curb and Gutter
	Minor Demolition for Remodeling	G2026	Parking Lot Appurtenances
F2012	Selective Structural Demolition	~	
			Pedestrian Paving
F2012	Hazardous Components	G2031	Pedestrian Paving Base Courses
		G2031 G2032	Pedestrian Paving Base Courses Flexible Pedestrian Pavement
F202	Hazardous Components Abatement	G2031 G2032 G2033	Pedestrian Paving Base Courses Flexible Pedestrian Pavement Pedestrian Unit Pavers
F202	Hazardous Components	G2031 G2032 G2033 G2034	Pedestrian Paving Base Courses Flexible Pedestrian Pavement Pedestrian Unit Pavers Rigid Pedestrian Paving
F202 G BUI	Hazardous Components Abatement LDING SITEWORK	G2031 G2032 G2033 G2034	Pedestrian Paving Base Courses Flexible Pedestrian Pavement Pedestrian Unit Pavers
F202 G BUII G10	Hazardous Components Abatement  LDING SITEWORK  SITE PREPARATION	G2031 G2032 G2033 G2034 G2035	Pedestrian Paving Base Courses Flexible Pedestrian Pavement Pedestrian Unit Pavers Rigid Pedestrian Paving Exterior Steps
F202 G BUII G10 G101	Hazardous Components Abatement  LDING SITEWORK  SITE PREPARATION Subsurface Investigation	G2031 G2032 G2033 G2034 G2035	Pedestrian Paving Base Courses Flexible Pedestrian Pavement Pedestrian Unit Pavers Rigid Pedestrian Paving Exterior Steps  Site Development
F202  G BUIL  G10 G101 G1011	Hazardous Components Abatement  LDING SITEWORK  SITE PREPARATION Subsurface Investigation Standard Penetration Tests	G2031 G2032 G2033 G2034 G2035 G204 G2041	Pedestrian Paving Base Courses Flexible Pedestrian Pavement Pedestrian Unit Pavers Rigid Pedestrian Paving Exterior Steps  Site Development Fountains
F202  G BUIL  G10 G101 G1011	Hazardous Components Abatement  LDING SITEWORK  SITE PREPARATION Subsurface Investigation	G2031 G2032 G2033 G2034 G2035 G204 G2041 G2042	Pedestrian Paving Base Courses Flexible Pedestrian Pavement Pedestrian Unit Pavers Rigid Pedestrian Paving Exterior Steps  Site Development Fountains Fences and Gates
<b>G10 G101</b> G1011 G1012	Hazardous Components Abatement  LDING SITEWORK  SITE PREPARATION Subsurface Investigation Standard Penetration Tests Seismic Investigation	G2031 G2032 G2033 G2034 G2035 G204 G2041 G2042 G2043	Pedestrian Paving Base Courses Flexible Pedestrian Pavement Pedestrian Unit Pavers Rigid Pedestrian Paving Exterior Steps  Site Development Fountains Fences and Gates Recreational and Sports Facilities
F202  G BUII  G10  G101  G1011  G1012  G102	Hazardous Components Abatement  LDING SITEWORK  SITE PREPARATION Subsurface Investigation Standard Penetration Tests Seismic Investigation  Site Clearing	G2031 G2032 G2033 G2034 G2035 G204 G2041 G2042 G2043 G2044	Pedestrian Paving Base Courses Flexible Pedestrian Pavement Pedestrian Unit Pavers Rigid Pedestrian Paving Exterior Steps  Site Development Fountains Fences and Gates Recreational and Sports Facilities Site and Street Furnishings
<b>G10 G101</b> G1011 G1012 <b>G102</b> G1021	Hazardous Components Abatement  LDING SITEWORK  SITE PREPARATION Subsurface Investigation Standard Penetration Tests Seismic Investigation  Site Clearing Sod Stripping	G2031 G2032 G2033 G2034 G2035 G204 G2041 G2042 G2043 G2044 G2045	Pedestrian Paving Base Courses Flexible Pedestrian Pavement Pedestrian Unit Pavers Rigid Pedestrian Paving Exterior Steps  Site Development Fountains Fences and Gates Recreational and Sports Facilities Site and Street Furnishings Exterior Signs
<b>G10 G101</b> G1011 G1012 <b>G102</b> G1021 G1022	Hazardous Components Abatement  LDING SITEWORK  SITE PREPARATION Subsurface Investigation Standard Penetration Tests Seismic Investigation  Site Clearing Sod Stripping Clearing and Grubbing	G2031 G2032 G2033 G2034 G2035 G204 G2041 G2042 G2043 G2044 G2045 G2046	Pedestrian Paving Base Courses Flexible Pedestrian Pavement Pedestrian Unit Pavers Rigid Pedestrian Paving Exterior Steps  Site Development Fountains Fences and Gates Recreational and Sports Facilities Site and Street Furnishings Exterior Signs Footbridges and Underpasses
<b>G10 G101</b> G1011 G1012 <b>G102</b> G1021 G1022	Hazardous Components Abatement  LDING SITEWORK  SITE PREPARATION Subsurface Investigation Standard Penetration Tests Seismic Investigation  Site Clearing Sod Stripping	G2031 G2032 G2033 G2034 G2035 G204 G2041 G2042 G2043 G2044 G2045 G2046 G2047	Pedestrian Paving Base Courses Flexible Pedestrian Pavement Pedestrian Unit Pavers Rigid Pedestrian Paving Exterior Steps  Site Development Fountains Fences and Gates Recreational and Sports Facilities Site and Street Furnishings Exterior Signs Footbridges and Underpasses Flagpoles
<b>G10 G101</b> G1012 <b>G102</b> G1021 G1022 G1022 G1023	Hazardous Components Abatement  LDING SITEWORK  SITE PREPARATION Subsurface Investigation Standard Penetration Tests Seismic Investigation  Site Clearing Sod Stripping Clearing and Grubbing Shrub and Tree Removal	G2031 G2032 G2033 G2034 G2035 G204 G2041 G2042 G2043 G2044 G2045 G2046 G2047	Pedestrian Paving Base Courses Flexible Pedestrian Pavement Pedestrian Unit Pavers Rigid Pedestrian Paving Exterior Steps  Site Development Fountains Fences and Gates Recreational and Sports Facilities Site and Street Furnishings Exterior Signs Footbridges and Underpasses
G10 G101 G1011 G1012 G1022 G1021 G1022 G1023 G103	Hazardous Components Abatement  LDING SITEWORK  SITE PREPARATION Subsurface Investigation Standard Penetration Tests Seismic Investigation  Site Clearing Sod Stripping Clearing and Grubbing Shrub and Tree Removal  Site Demolition and Relocations	G2031 G2032 G2033 G2034 G2035 G204 G2041 G2042 G2043 G2044 G2045 G2046 G2047 G2048	Pedestrian Paving Base Courses Flexible Pedestrian Pavement Pedestrian Unit Pavers Rigid Pedestrian Paving Exterior Steps  Site Development Fountains Fences and Gates Recreational and Sports Facilities Site and Street Furnishings Exterior Signs Footbridges and Underpasses Flagpoles Covers and Shelters
G10 G101 G1011 G1012 G1022 G1022 G1023 G103 G1031	Hazardous Components Abatement  LDING SITEWORK  SITE PREPARATION Subsurface Investigation Standard Penetration Tests Seismic Investigation  Site Clearing Sod Stripping Clearing and Grubbing Shrub and Tree Removal  Site Demolition and Relocations Building Demolition	G2031 G2032 G2033 G2034 G2035 G204 G2041 G2042 G2043 G2044 G2045 G2046 G2047 G2048	Pedestrian Paving Base Courses Flexible Pedestrian Pavement Pedestrian Unit Pavers Rigid Pedestrian Paving Exterior Steps  Site Development Fountains Fences and Gates Recreational and Sports Facilities Site and Street Furnishings Exterior Signs Footbridges and Underpasses Flagpoles Covers and Shelters  Landscaping
F202  G BUII  G10 G101 G1011 G1012 G102 G1021 G1022 G1023 G103 G1031 G1032	Hazardous Components Abatement  LDING SITEWORK  SITE PREPARATION Subsurface Investigation Standard Penetration Tests Seismic Investigation  Site Clearing Sod Stripping Clearing and Grubbing Shrub and Tree Removal  Site Demolition and Relocations Building Demolition Site Elements Demolition	G2031 G2032 G2033 G2034 G2035 G204 G2041 G2042 G2043 G2044 G2045 G2046 G2047 G2048 G205 G2051	Pedestrian Paving Base Courses Flexible Pedestrian Pavement Pedestrian Unit Pavers Rigid Pedestrian Paving Exterior Steps  Site Development Fountains Fences and Gates Recreational and Sports Facilities Site and Street Furnishings Exterior Signs Footbridges and Underpasses Flagpoles Covers and Shelters  Landscaping Irrigation Systems
F202  G BUIL  G10  G101  G1012  G102  G1022  G1023  G1033  G1031  G1032  G1033	Hazardous Components Abatement  LDING SITEWORK  SITE PREPARATION Subsurface Investigation Standard Penetration Tests Seismic Investigation  Site Clearing Sod Stripping Clearing and Grubbing Shrub and Tree Removal  Site Demolition and Relocations Building Demolition Site Elements Demolition Structure Relocation	G2031 G2032 G2033 G2034 G2035 G204 G2041 G2042 G2043 G2044 G2045 G2046 G2047 G2048 G205 G2051 G2052	Pedestrian Paving Base Courses Flexible Pedestrian Pavement Pedestrian Unit Pavers Rigid Pedestrian Paving Exterior Steps  Site Development Fountains Fences and Gates Recreational and Sports Facilities Site and Street Furnishings Exterior Signs Footbridges and Underpasses Flagpoles Covers and Shelters  Landscaping Irrigation Systems Shrub and Tree Transplanting
F202  G BUIL  G10  G101  G1012  G102  G1022  G1023  G1033  G1031  G1032  G1033	Hazardous Components Abatement  LDING SITEWORK  SITE PREPARATION Subsurface Investigation Standard Penetration Tests Seismic Investigation  Site Clearing Sod Stripping Clearing and Grubbing Shrub and Tree Removal  Site Demolition and Relocations Building Demolition Site Elements Demolition	G2031 G2032 G2033 G2034 G2035 G204 G2041 G2042 G2043 G2044 G2045 G2046 G2047 G2048 G205 G2051 G2052 G2053	Pedestrian Paving Base Courses Flexible Pedestrian Pavement Pedestrian Unit Pavers Rigid Pedestrian Paving Exterior Steps  Site Development Fountains Fences and Gates Recreational and Sports Facilities Site and Street Furnishings Exterior Signs Footbridges and Underpasses Flagpoles Covers and Shelters  Landscaping Irrigation Systems Shrub and Tree Transplanting Soil Preparation
F202  G BUIL  G10  G101  G1012  G102  G1022  G1023  G1033  G1031  G1032  G1033	Hazardous Components Abatement  LDING SITEWORK  SITE PREPARATION Subsurface Investigation Standard Penetration Tests Seismic Investigation  Site Clearing Sod Stripping Clearing and Grubbing Shrub and Tree Removal  Site Demolition and Relocations Building Demolition Site Elements Demolition Structure Relocation	G2031 G2032 G2033 G2034 G2035 G204 G2041 G2042 G2043 G2044 G2045 G2046 G2047 G2048 G2051 G2052 G2053 G2054	Pedestrian Paving Base Courses Flexible Pedestrian Pavement Pedestrian Unit Pavers Rigid Pedestrian Paving Exterior Steps  Site Development Fountains Fences and Gates Recreational and Sports Facilities Site and Street Furnishings Exterior Signs Footbridges and Underpasses Flagpoles Covers and Shelters  Landscaping Irrigation Systems Shrub and Tree Transplanting Soil Preparation Lawns and Grasses
F202  G BUII  G10 G101 G1011 G1012 G102 G1021 G1022 G1023 G103 G1031 G1032 G1033 G1034 G104	Hazardous Components Abatement  LDING SITEWORK  SITE PREPARATION Subsurface Investigation Standard Penetration Tests Seismic Investigation  Site Clearing Sod Stripping Clearing and Grubbing Shrub and Tree Removal  Site Demolition and Relocations Building Demolition Site Elements Demolition Structure Relocation Utility Relocation	G2031 G2032 G2033 G2034 G2035 G204 G2041 G2042 G2043 G2046 G2047 G2048 G205 G2051 G2052 G2053 G2054 G2055	Pedestrian Paving Base Courses Flexible Pedestrian Pavement Pedestrian Unit Pavers Rigid Pedestrian Paving Exterior Steps  Site Development Fountains Fences and Gates Recreational and Sports Facilities Site and Street Furnishings Exterior Signs Footbridges and Underpasses Flagpoles Covers and Shelters  Landscaping Irrigation Systems Shrub and Tree Transplanting Soil Preparation

Chapter 5 Index of Details 25

G206	Hazardous Waste Remediation	G4011	Site Steam Piping Systems
G2061	Containment Systems	G4012	Site Steam Distribution Equipment
G2062	Extraction/Leachate Collection		
	Systems	G402	Site Hydronic Distribution
G2063	Monitoring Systems		Systems
G2064	Decontamination Systems	G4021	Site Hydronic Piping Systems
		G4022	Site Hydronic Distribution
G30	SITE PLUMBING UTILITIES		Equipment
G301	Site Water Supply and Distribution		
	Systems	G50	SITE ELECTRICAL UTILITIES
	Water Wells	G501	
G3012	Site Domestic Water Distribution	G5011	Site Electrical Substations
G3013	Site Fire Protection Water Distribution Systems	G5012	Site Electric Power Distribution Lines
G3014	Site Contaminated Water	G5013	Site Electric Power Transmission
	Distribution		Equipment
G302	· ·	G502	8 8 V
G3021	Site Sanitary Sewerage	G5021	Area Site Lighting Systems
G3022	Septic Systems	G5022	Security Site Lighting Systems
G3023	Site Sanitary Sewerage Equipment	G5023	Other Site Lighting Systems
G3024	Sewage Ponds		
		G503	Site Communication and Security
G303	Site Storm Sewer Systems		Systems
	Site Storm Sewerage		Misc. Systems
	Site Storm Sewer Appurtenances		Site Alarm and Detection Systems
	Site Storm Sewerage Equipment		Site Voice and Data Systems
G3034	Storm Water Ponds and Reservoirs		Site Television Systems
		G5034	Site TV Security Monitoring
G304	·		Systems
	Site Gas Distribution Systems	G5035	Site Security Sensor Systems
	Site Oil Distribution Systems		
G3043	Other Site Fuel Distribution	G505	Other Site Electrical Systems
	Systems	G5051	Cathodic Protection Systems
C205	Site Special Dlumbing Systems	G60	OTHER SITE CONSTRUCTION
G305	Site Special Plumbing Systems	G601	
	Industrial Waste Systems		Service Tunnels Other Site Systems and
G3032	Other Special Site Plumbing	G602	Other Site Systems and
	Systems	C6021	Equipment
C40	CITE HEATING VENTUATING	G0021	Contaminant Processing Systems
G40	SITE HEATING, VENTILATING, AND AIR CONDITIONING		and Equipment
C401	(HVAC) UTILITIES Site Steem Distribution Systems		
G4010	Site Steam Distribution Systems Misc. Site Steam Distribution		
14010	IVERC ARE ARRIH DISTRIBUTION		

Systems

# 6 Inch-Pound Library

The following pages contain images of the CADD Details Library. The details presented are accessible through the Center-supplied retrieval programs. Loading instructions are provided as part of the electronic media. Appendix C contains a form for recommending changes to specific details within the CADD Details Library.

Note: Because these details represent existing details used within the DoD, it should be noted that the level/layer assignments, colors, and line weights for some details do not meet the prescribed standards set forth in this manual. Subsequent versions of the CADD Details Library will continue to convert details to meet the prescribed standards.

## 7 Metric Library

The following pages contain images of the CADD Details Library. The details presented are accessible through the Center-supplied retrieval programs. Loading instructions are provided as part of the electronic media. Appendix C contains a form for recommending changes to specific details within the CADD Details Library.

Note: Because these details represent existing details used within the DoD, it should be noted that the level/layer assignments, colors, and line weights for some details do not meet the prescribed standards set forth in this manual. Subsequent versions of the CADD Details Library will continue to convert details to meet the prescribed standards.

Chapter 7 Metric Library 301

# **Appendix A Abbreviations for CADD Details Library**

Abbreviation	Definition	Abbreviation	Definition
(N)	new	AMB	ambient
(R)	relocated item	AMP	ampere
<	angle	ANC	anchor, anchorage
1/4 RD	quarter round	ANOD	anodized
A/C	air conditioning	ANSI	American National Standards Institute
A.C.	alternating current	AP	access panel
A.L.	active leaf	APPD	1
AB	anchor bolt	APPROX	approved
ABV	above	ARCH	approximate
ACC	access		architect(ural)
ACI	American Concrete Institute	ARI	American Refrigeration Institute
ACPL	acoustical plaster	ASB	asbestos
ACR	acrylic plastic	ASC	above suspended ceiling
ACSR	aluminum conductor steel reinforced	ASPH	asphalt
ACST	acoustic	AT, ACT	acoustical (ceiling) tile
ACU	air conditioning unit	ATC	acoustical tile ceiling
	e e e e e e e e e e e e e e e e e e e	AUTO	automatic
ADD ADD	access door addendum	AVG	average
ADH	adhesive	AWC	acoustical wall covering
		AWG	American wire gauge
ADJ	adjacent, adjunct	В	bins
ADJT	adjustable	B.M.	bench mark
ADO	automatic door operator	BATT INSUL	batt insulation
AFF	above finished floor	BBD	bulletin board
AGG	aggregate	BC	bookcase
AHU	air handling unit	BD	board
AI	area inlet	BDY	boundary
AIC	amps interrupting capacity (sym rms)	BE	bench
AISC	American Institute of Steel Construction	BEJ	brick expansion joint
ALT	alternate	BEL	below
ALUM	aluminum	BIT	bituminous

Abbreviation	Definition	Abbreviation	Definition
ВЈТ	bed joint	CHAM	chamfer
BL	building line	CHBD	chalkboard
BLDG	building	CHIM	chimney
BLK	block	CHT	ceiling height
BLKG	blocking	CI	cast iron
BM	beam	CIPC	cast-in-place concrete
ВО	bottom of	CIR	circular
BOT	bottom	CIRC	circumference
BP	back plaster(ed)	CJT	control joint
BPL	bearing plate	CKD	checked
BPR	bed pan and urinal rack	CKT	circuit
BRCG	bracing	CL WG	clear wire glass
BRDG	bridging	CL	center line
BRG	bearing	CLG	ceiling
BRK	brick	CLGL	clear glass
BRKT	bracket	CLKG	caulking
BRZ	bronze	CLL	contract limit line
BS	both sides	CLO	closet
BSMT	basement	CLOS	closed
ВТ	bent	CLR	clear(ance)
BTU	British thermal unit	CLS	closure
BTUH	btu per hour	CM	centimeter(s)
BTW	between	CMP	corrugated metal pipe
BUR	built-up roofing	CMT	ceramic mosaic (tile)
BVL	beveled	CMU	concrete masonry unit
BW	both ways	CND	conduit (for raceway-elec. sheets)
C to C	center to center	CNL	conductive neoprene latex
C.B.	circuit breaker	CNTR	counter
C.I.	curb inlet	CO	cleanout
C.T.	current transformer	CO2	carbon dioxide
CAB	cabinet	COL	column
CAD	cadmium	COM	common
CAP	capacity	COMB	combustion
CB	catch basin	COMP	compress(ed)(ion)(ible)
CCT	cubicle curtain track	COMPO	composite, composition
CCU	coronary care unit	COMPT	compartment
CE	cover elevation	CONC	concrete
CEM	cement	CONN	connection
CER	ceramic	CONST	construction
CFI	conductive flooring	CONST JT	construction joint
CFL	counterflashing	CONT	continue (ous)
CFM	cubic feet per minute	CONTR	contract(or)
CFT	cubic foot	COR	corner
CG	corner guard		

Abbreviation	Definition	Abbreviation	Definition
CORR	corrugated	DH	duct heater
CORR.	corridor	DIA	diameter
COV	covered	DIAG	diagonal
CP, CPT	carpet(ed)	DIM	dimension
CPL	cement plaster	DISC	disconnect
CPR	copper	DISP	dispenser
CPS	cycles per second (hertz)	DIST	distribution
CR	chromium (plated)	DIV	division
CRES	corrosive resistant steel	DL	dead load
CRG	cross grain	DMT	demountable
CRS	course(s)	DN	down
CSK	countersink, countersunk	DP	dampproofing
CSMT	casement	DPR	damper
CST	cast stone	DR	door
СТ	ceramic tile	DRB	drainboard
CTL	carpet tile	DRN	drain
CTP	ceramic tile panel	DS	downspout
CTR	center	DSB	double strength "b" quality glass
CTSK	countersunk screw	DT	drain tile
CU	condensing unit	DTA	dovetail anchor
CU YD	cubic yards	DTL, DET	detail
CUH	cabinet unit heater	DTS	dovetail anchor slot
CV	ceiling vent	DW	dumbwaiter
CVH	conductive vinyl homogen- eous (sheet type)	DWG	drawing
CW	cold water	DWGS	drawings
CYL	cylinder	DWLS	dowels
d	penny (as in nail - 10d)	DWR	drawer
D	datum	DX	direct expansion
D.H.	double hung	Е	east
D&M	dressed and matched	E.P.	electric panelboard
DA	double acting	EA	exhaust air
DB	dry bulb	EA.	each
DBL	double	EAT	entering air temperature
DC	dental casework	ЕВ	expansion bolt
DCJ	doweled control joint	EEG	electro encephalographic
DCJT	dummy control joint	EF	each face
DCL	door closer	EJ	expansion joint
DEG	degree	EKG	electrocardiograph
DEM	demolish	EL, ELEV	elevation - grade or building
DEP	depressed	ELEC	electric or electrical
DEPR	depression	EMD	estimated maximum demand
DEPT	department	EMER	emergency
DF	drinking fountain	ENCL	enclose(ure)

Abbreviation	Definition	Abbreviation	Definition
ENT	ear, nose, and throat	FH	flathead or flushhead
ENTR	entrance, entering	FHC	fire hose cabinet
EP	explosion proof	FHMS	flathead machine screw
EPY	epoxy coating	FHR	fire hose rack
EQ	equal	FHS	fire hose station
EQUIP	equipment	FHWS	flathead wood screw
ESC	escalator	FI	film illuminator
EST	estimate(d)	FIG	figure
EWC	electric water cooler	FIN	finish(ed)
EWT	entering water temperature	FIX	fixture
EXCA	excavate	FJT	flush joint
EXD	exit device	FL	floor
EXH	exhaust	FLASH	flashing
EXIST	existing	FLCO	floor cleanout
EXMP	expanded metal plate	FLEX	flexible
EXP	exposed, expansion	FLG	flooring
EXPL	explosion	FLR	floor
EXPN	expansion	FLUOR	fluorescent
EXS	extra strong	FN	fence
EXT	exterior	FOC	face of concrete
F	Fahrenheit	FOF	face of finish
F.D.	fire damper	FOM	face of masonry
F.H.	fire hydrant	FOS	face of studs
FA	fire alarm	FP	fire partition
FAC	fire apparatus closet	FPL	floor plate
FAI	fresh air intake	FPM	feet per minute
FAS	fasten(er)	FPRF	fireproof
FB	face brick	FR	frame(d)(ing)
FBD	fiberboard	FRA	fresh air
FBO	furnished by others	FRC	fire-resistant coating
FBRK	fire brick	FRG	forged
FC	foot-candle	FRT	fire-retardant
FCG	facing	FS	full size
FCJ	floor construction joint	FT	feet
FCU	fan coil unit	FTG	footing
FD	floor drain	FUR	furr(ed)(ing)
FDN	foundation	FUT	future
FE	fire extinguisher	FW	fire water
FEB	fire extinguisher bracket	FWC	fabric wall covering
FEC	fire extinguisher cabinet	G	gas
FF	factory finish	GA	gage or gauge
FFE	finished floor elevation	GAL	gallon(s)
FFL	finished floor line	GALV	galvanized
FGL, F.G.	fiberglass	GB	grab bar

Abbreviation	Definition	Abbreviation	Definition
GC	general contract(or)	HDR	header
GCMU	glazed concrete masonry	HDRL	handrail
CCO	units	HDW	hardware
GCO	ground cleanout	HES	high early-strength cement
GEN GF	general	НН	handhole
	ground face	HIP	high pressure
GFE	government-furnished equipment	НЈТ	head joint
GFE/CI	government-furnished equip- ment contractor installed	HK	hook(s)
GFI	ground fault interrupter	HOR	horizontal
GI	galvanized iron	HP	horsepower
GKT	gasket(ed)	HPT	high point
GL	glass, glazing	HR	hour
GLB	glass block	HS	high strength
GLF	glass fiber	HSGYP	high-strength gypsum plaster
GND	ground	HT	height
GOVT	government	HTG	heating
GP	galvanized pipe	HTR	heater
GPDW	gypsum drywall	HVAC	heating, ventilating and air conditioning
GPL	gypsum lath	HWD	hardwood
GPM	gallons per minute	HWH	hot water heater
GPPL	gypsum plaster, finish floor	HX	hexagonal
GPT	gypsum tile	HYD	hydraulic
GR	grade(ing)	HZ	hertz
GRN	granite	I	iron
GRS	galvanized rigid steel conduit	I.D.	inside diameter
GRTG	grating	IC	intercom
GSS	galvanized steel sheet	ICU	intensive care unit
GST	glazed structural tile	IES	illuminating engineering
GSU	glazed structural units	H IZ	society
GT	grout	ILK	interlock
GVL	gravel	IN	inch incinerator
GWB	gypsum wallboard	INCIN INCL	
GWT	glazed wall tile		include(d)(ing)
GYP	gypsum	INSC	insulating concrete
H.D.	heavy duty	INSF	insulating fill
H.M.	hollow metal	INSUL INSUL	insulation
H'CAP	handicapped	INSUL'D	insulated
HAC	housekeeping aide's closet	INT	interior
НВ	hose bibb	INTM	intermediate
HBD	hardboard	INV	invert(ed)
НС	hollow core	IP	iron pipe
HCD	halon containment damper	IPS	iron pipe size
HD	head	I.P.S.	inside pipe size

Abbreviation	Definition	Abbreviation	Definition
IV	intravenous	LPS	lightproof shade
JB	junction box	LPT	low point
JC	janitor's closet	LR	living room
JCT	junction	LT WT	lightweight
JF	joint filler	LT	light
JST	joist	LTG	lighting
JT	joint	LVR	louver
KCM	kilo circular mil	LWC	lightweight concrete
KCPL	Keene's cement plaster	LWT	leaving water temperature
KIP	kilopound (1000 pounds)	M	meter(s)
KIT	kitchen	M&B	matched and beaded
KL	key lock	MACH	machine
КО	knockout	MAS	masonry
KPL	kickplate	MAX	maximum
KV	kilovolts	MB	machine bolts
KVA	kilovolt amperes	MBR	member
KVAR	kilovolt amperes reactive	MCJ	masonry control joint
KW	kilowatt	MCO	metal-cased opening
L	lumen	MDS	metal divider strip
L.H.	left hand(ed)	MECH	mechanic(al)
LAB	laboratory	MED	medium
LAD	ladder	MEDCAB	medical cabinet
LAM	laminate(d)	MER	mechanical equipment room
LAT	leaving air temperature	MES	metal edge strip
LAU	laundry	MET	metal
LAV	lavatory	MFD	metal floor decking
LB	lag bolt	MFG	manufacturing
LBL	label	MFR	manufacture(er)
LBR	lumber	MGT	matte-glazed tile
LBS	pounds	MG	motor generator
LC	light control	MH	manhole
LD	load	MI	malleable iron
LDG	loading	MIN	minimum
LG	length	MIR	mirror
LIN	linear	MISC	miscellaneous
LIS	lawn irrigation system	ML	metal lath
LKR	locker	MLDG	moulding
LL	live load	MM	millimeter(s)
LLD	lead-lined door	MMB	membrane
LMS	limestone	MNIC	material not in contract
LNTL	lintel		(installation by contractor)
LONG	longitudinal	MO	masonry opening
LP	lightproof	MOD	modular
LPD	lightproof door	MOD.	modified

Abbreviation	Definition	Abbreviation	Definition
MONO	monolithic	OHMS	ovalhead machine screw
MOT	motor	OHWS	ovalhead wood screw
MOV	movable	OJ	open-web joist
MP	movable partition	OP	opaque
MR	mop receptor	OPH	opposite hand
MRB	marble	OPNG	opening
MRD	metal roof decking	OPP	opposite
MS	machine screws	OPS	operations
MSTC	mastic	OR	observation riser
MTD	mount(ed)(ing)	OS & Y	outside screw and yoke
MTFR	metal furring	OT	occupational therapy
MTHR	metal threshold	OW	observation window
MTL	material(s)	P	pole
MULL	mullion	P.L.	property line
MWK	millwork	P.S.	pressed steel
N	north	PA	public address
N.C.	normally closed	PAR	parallel
N.L.	neoprene latex	PART'N(S)	partition(s)
N.O.	normally open	PB	panic bar
N'REQD	not required	PBD	particle board
NAT	natural	PBPU	patient's bedside power unit
NEC	national electrical code	PBS	push button station
NEMA	National Electrical Manu- facturer's Association	PC	piece
NFPA	National Fire Protection	PCC	precast concrete
MIA	Association	PCF	pounds per cubic foot
NI	nickel	PCPL	cement plaster (portland)
NIC	not in contract	PD	pavement drain
NL	nailable	PE	porcelain enamel
NMT	nonmetallic	PED	pedestal
NO.	number	PERF	perforate(d)
NOM	nominal	PERI	perimeter
NP	neuropsychiatric	PFL	pounds per lineal foot
NR	noise reduction	PG	plate glass
NRC	noise reduction coefficient	PH	phase
N.T.S.	not to scale	PHAR	pharmacy
O.D.	outside diameter	PI	point of intersection
OA	outside air	PIPU	prefab isolation power unit
OB WG	obscure wire glass	PIV	post indicating valve
OBGL	obscure glass	PK	parking
OBSC	obscure	PL	plate
OC	on center(s)	PLAS	plaster
OCEW	on center each way	PLAS LAM	plastic laminate
OFF	office	PLATF	platform
ОН	overhead	PLBG	plumbing

Abbreviation	Definition	Abbreviation	Definition
PLG	piling	RCP	reinforced concrete pipe
PLYWD	plywood	RCVR	receiver
PNL	panel	RDGE	ridge
PNT	paint(ed)	RECEP	receptacle
POL	polish	RECR	recreation
PORC	porcelain	RECT	rectifier
PORT	portable	REF	reference
PPG	polished plate glass	REFR	refrigerator
PPM	parts per million	REG	reglet
PR	pair	REG.	register
PREFAB	prefabricate(d)	REINF	reinforcing, reinforced, reinforcement
PREFIN	prefinished	DEM	
PRF	preformed	REM	remove(able)
PROJ	project	REQ'D, REQD	required
PRV	pressure-regulating valve	RESIL	resilient
PS	pipe space	RET	return
PSC	prestressed concrete	REV	revision(s), revised
PSF	pounds per square foot	RFG RFH	roofing roof hatch
PSI	pounds per square inch		
PT	pneumatic tube	RFL	reflect(ed)(ive)(or)
PT.	point	RGE	range
PTC	post-tensioned concrete	RGH	rough
PTD	paper towel dispenser	RH RK	relative humidity
PTR	paper towel receptor	RL	
PV	pave(d)(ing)	RM	rail(ing)
PVC	polyvinylchloride	RND	room
PVMT	pavement	RO	round rough opening
PW	pass window	ROW	right of way
QT	quarry tile	RP	retractable partition
QT.	quart	RPM	revolutions per minute
QTRS	quarters	RPRT	raised pattern rubber tile
QTY	quantity	RSR	riser
R.D.	roof drain	RT	rubber tile
R.H.	right hand(ed)	RUB	rubber
R&S	casework in clergy room and sacristy, chaplain service	RVS	reverse (side)
RA	return air	RVT	rivet
RAD	radius	RWC	rainwater conductor
RAG	return air grille	S	south
RAR	return air register	S.B.	security bars
RB	rubber base, resilient base	S.C.	special coating
RBL	rubble stone	S&R	shelf and rod
RBT	rabbet, rebate	SA	supply air
RC	remote control	SB	splash block

Abbreviation	Definition	Abbreviation	Definition
SC	solid core	STD	standard
SCHED	schedule	STG	seating
SCI	spinal cord injury	STGR	stringer
SCN	screen	STL	steel
SCR	screw	STN	stone
SCT	structural clay tile	STOR	storage
SCUT	scuttle	STRL	structural
SD	storm drain	STWY	stairway
SDI	Steel Door Institute	SUB FL	subfloor
SECT	section	SUSP	suspended
SECY	secretary	SVF	sheet vinyl flooring
SEQ	sequence	SW	switch
SFGL	safety glass	SWBD	switchboard
SFTU	structural facing tile unit	SYM	symmetrical
SFU	structural facing unit	SYN	synthetic
SG	sheet glass	SYS	system
SH	shelf, shelving	T	tread
SHLD	shoulder	T'STAT	thermostat
SHO	shore(d)(ing)	T&G	tongue and groove
SHT	sheet	TA	table
SHTG	sheathing	TAN	tangent
SIM	similar	TB	towel bar
SJI	Steel Joist Institute	TC	terra cotta
SKL	skylight	TEL	telephone
SL	sleeve	TEMP	temperature
SM	sheet metal	TEMP.	temporary
SMS	sheet metal screws	TERM	terminal
SNT	sealant	TERR	terrazzo
SOV	shut off valve	TGL	toggle
SP	static pressure	TH	truss head
SPC	spacer	THK	thick(ness)
SPD	soundproof door	THR	threshold
SPEC(S)	specification(s)	TKBD	tackboard
SPF	soundproof	TKS	tackstrip
SPH	space heater	TO	top of
SPKR	speaker	TOIL	toilet
SPL	special	TOL	tolerance
SQ	square	TOPO	topography
SQHD	square head	TPD	toilet paper dispenser
SQUAD	squadron	TPTN	toilet partition
SS, SST	stainless steel	TR	transom
SSK	service sink	TRANS	transverse
SSMR	standing seam metal roofing	TSL	top of slab
STA	station	TST	top of steel

Abbreviation	Definition	Abbreviation	Definition
TT	terrazzo tile resinous matrix	VTR	vent thru roof
TV	television	VWC	vinyl wall covering
TW	top of wall	W	west
TYP	typical	W/	with
UC	unit cooler	W/O	without
UG	underground	W/C	wheelchair
UH	unit heater	W.D.	waste drain
UL	Underwriters Laboratories	W.S.	waste stack
UNEX	unexcavated	WB	wet bulb
UNFIN	unfinished	WC	water closet
UPS	uninterruptable power system	WCO	wood-cased opening
UR	urinal	WD BLK	wood blocking
UT		WD	wood
	utility	WD DR	wood door
UV V	unit ventilator volt	WF	wire flange
		WG	wire glass
V.T.	voltage transformer	WH	wall hung
VA	vinyl asbestos	WHB	wheel bumper
VAB	vapor barrier	WHM	watthour meter
VAR	varnish	WHT	white
VAT	vinyl asbestos tile	WI	wrought iron
VB VGD	vinyl base	WIN	window
VCP	vitrified clay pipe	WKSH	work shop
VCT	vinyl composition tile	WM	wire mesh
VD	vault door	WP	weatherproof
VENT	ventilator(tion)	WPF, WPFG	water proof(ing)
VERT	vertical	WPT	working point
VEST	vestibule	WR	waste receptacle
VF	vinyl fabric	WRB	wardrobe
VG	vertical grain	WS	waterstop
VH	vinyl homogeneous	WSCT	wainscot
VIN	vinyl	WT	weight
VJ	v-joint(ed)	WTH	width
VL	clinical laboratory equipment	WTW	wall to wall
VNR	veneer	WWF	welded wire fabric
VOL	volume	WWM	woven wire mesh
VR	radio isotope lab equipment	X	X-ray equipment radiology
VRM	vermiculite	XFMR	transformer
VS	vent stack	Y.D.	yard drain
VT	vinyl tile	YD	yard
VT	vinyl tile	YD	yard

## Appendix B Metric Construction Information

The following information was originally published in the Construction Metrication Council's Metric in Construction newsletter. Volume 3. Issue 3. dated May-June 1994. Metric in Construction is a bimonthly newsletter designed to inform the building community about metrication in U.S. construction. The Construction Metrication Council was created by the National Institute of Building Sciences to provide industry-wide, public, and private sector support for the metrication of Federal construction and to promote the adoption and use of the metric system of measurement as a means of increasing the international competitiveness, productivity, and quality of the U.S. construction industry. The current Chairman of the Council is Mr. Thomas R. Rutherford. P.E., DoD, and the Executive Director is Mr. William A. Brenner, AIA. The Center would like to thank Mr. Brenner for allowing the reprint of the Council's newsletter information. For information on how to subscribe to Metric in Construction, please address all inquiries to the following:

> Construction Metrication Council National Institute of Building Sciences 1090 Vermont Avenue, N.W., Suite 700 Washington, D.C. 20005-4905 Telephone: (202) 289-7800

FAX: (202) 289-1092 Internet: www.nibs.org

# ONE MORE TIME: WHAT WILL CHANGE AND WHAT WILL STAY THE SAME?

#### **METRIC MODULE AND GRID**

What will change

- The basic building module, from 4 inches to **100 mm**.
- The planning grid, from 2' x 2' to 600 x 600 mm.

What will stay the same

• A module and grid based on rounded, easy-to-use dimensions.

#### **DRAWINGS**

What will change

Units, from feet and inches to millimeters for all building dimensions and to meters for large site plans and civil engineering drawings. Unit notations are unnecessary: if there's no decimal point, it's millimeters; if there's a decimal point carried to one, two, or three places, it's meters. Centimeters are not used in construction.

- Drawing scales, from inch-fractions-to-feet to true ratios. Preferred metric scales are **1:1** (full size); **1:5** (close to 3" = 1'-0"); **1:10** (between 1" = 1'-0" and 1-1/2" = 1'-0"); **1:20** (between 1/2" = 1'-0" and 3/4" = 1'-0"); **1:50** (close to 1/4" = 1'-0"); **1:100** (close to 1/8" = 1'-0"); **1:200** (close to 1/16" = 1'-0"); **1:500** (close to 1" = 40'-0"); **1:1000** (close to 1" = 80'-0").
- Drawing sizes, to the ISO "A" series:
  AO (1189 x 841 mm, 46.8 x 33.1 inches); A1 (841 x 594 mm, 33.1 x 23.4 inches); A2 (594 x 420 mm, 23.4 x 16.5 inches); A3 (420 x 297 mm, 16.5 x 11.7 inches); A4 (297 x 210 mm, 11.7 x 8.3 inches). Of course, metric drawings can be made on any size paper.

What will stay the same

Drawing contents.

**Never** use dual units (both inch-pound and metric) on drawings. It increases dimensioning time, doubles the chance for errors, makes drawings more confusing, and delays the learning process.

#### **SPECIFICATIONS**

What will change

Units of measure, from feet and inches to millimeters for linear dimensions, from square feet to square meters for area, from cubic yards to cubic meters for volume (except use liters for fluid volumes), and from other inch-pound units to metric units as appropriate.

What will stay the same

• Everything else in the specification.

Do not use dual units in specifications except when the use of an inch-pound measure serves to clarify an otherwise unfamiliar metric measure; then place the inch-pound unit in parentheses after the metric. For example, "7460 W (10 horsepower)." All unit conversions should be **checked by a professional** to ensure that rounding does not exceed allowable tolerances.

#### **FLOOR LOADS**

What will change

 Floor load designations, from "psf" to kilograms per square meter (kg/m²) for everyday use and kilonewtons per square meter (kN/m²) for structural calculations.

What will stay the same

• Floor load requirements.

Kilograms per square meter often are used to designate floor loads because many live and dead loads (furniture, filing cabinets, construction materials, etc.) are measured in kilograms. However, kilonewtons per square meter or their equivalent, megapascals, are the proper measure and should be used in structural calculations.

#### **CONSTRUCTION PRODUCTS**

What will change

- Modular products: brick, block, drywall, plywood, suspended ceiling components, and raised floors. They will undergo "hard" conversion; that is, their dimensions will change to new rounded "hard" metric numbers to fit the universal 600 x 600 mm metric planning grid.
- A number of other products, such as concrete reinforcing bars and various

kinds of fasteners. They are being converted to hard metric sizes as the result of industry initiatives.

 Products that are custom fabricated for each job (for example, cabinets, stairs, handrails, ductwork, commercial doors and windows, structural steel, and precast concrete) or pouredin-place (concrete). Such products usually can be made to any size, inchpound or metric, with equal ease so for metric jobs they simply will be fabricated or formed in metric.

#### What will stay the same

The balance of products, since they are cut-to-fit at the jobsite (for example, framing lumber, woodwork, wiring, piping, and roofing) or are not dimensionally sensitive (for example, fasteners, hardware, electrical components, plumbing fixtures, HVAC equip ment, and gravel). Such products will be just "soft" converted—that is, relabeled in metric. A 2-3/4" x 4-1/2" wall switch face plate will be relabeled 70 x 115 mm and a 30 gallon tank, 114 L. Eventually manufacturers may convert many of these products to new rounded "hard" metric sizes, but only when it becomes convenient to do so.

## "2-BY-4" STUDS AND OTHER "2-BY" FRAMING (BOTH WOOD AND METAL)

What will change

• Spacing, from 16" to **400 mm**, and 24" to **600 mm**.

What will stay the same

• Cross sections.

"2-bys" are produced in fractional inch dimensions now so there is no need to convert them to new rounded "hard" metric dimensions. 2-by-4s may keep their traditional name or perhaps they'll be relabeled a nominal 50 x 100 mm or a more exact size, such as 38 x 89 mm.

### DRYWALL, PLYWOOD, AND OTHER SHEET GOODS

What will change

- Widths, from 4'-0" to **1200 mm**.
- Heights, from 8'-0" to **2400 mm**, 10'-0" to **3000 mm**.

What will stay the same

 Thicknesses, so fire, acoustic, and thermal ratings won't have to be recalculated.

Metric drywall and plywood are readily available, but with a possible cost penalty for small orders. Metric rigid insulation may not be available at this time.

#### **BATT INSULATION**

What will change

 Nominal width labels, from 16" to 16"/400 mm and 25" to 24"/600 mm.

What will stay the same

• Everything else.

Batts will not change in width; they'll just have a tighter "friction fit" when installed among metric-spaced framing members.

#### **DOORS**

What will change

- Height, from 6'-8" to 2050 mm or 2100 mm and from 7'-0" to 2100 mm.
- Width, from 2'-6" to 750 mm, from 2'-8" to 800 mm, from 2'-10' to 850 mm, from 3'-0" to 900 mm or 950 mm, and from 3'-4" to 1000 mm.

What will stay the same

- Door thicknesses.
- Door materials and hardware.

For commercial work, doors can be ordered in any size since they normally are custom-fabricated.

#### **CEILING SYSTEMS**

What will change

Grids and lay-in ceiling tile, air diffusers, and lighting fixtures— from 2' x 2' to 600 x 600 mm and from 2' x 4' to 600 x 1200 mm.

What will stay the same

• Grid profiles, tile thicknesses, air diffuser capacities, florescent tubes, and means of suspension.

#### RAISED FLOOR SYSTEMS

What will change

• Grids and lay-in floor tile, from 2' x 2' to 600 x 600 mm.

What will stay the same

• Grid profiles, tile thicknesses, and means of support.

#### **HVAC CONTROLS**

What will change

• Temperature units, from Fahrenheit to Celsius.

What will stay the same

• All other parts of the controls.

Controls are now digital so temperature conversions can be made with no difficulty.

#### **BRICK**

What will change

- Standard brick to 90 x 57 x 190 mm.
- Mortar joints from 3/8" and 1/2" to 10 mm.
- Brick module from 2' x 2' to 600 x 600 mm.

What will stay the same

Brick and mortar composition.

Of the 100 or so brick sizes currently made, 5 to 10 are within a millimeter of a metric brick so the brick industry will have no trouble supplying metric brick.

#### **CONCRETE BLOCK**

What will change

• Block sizes to 190 x 190 x 390 mm.

- Mortar joints from 1/2" to **10 mm**.
- Block module from 2' x 2' to 600 x 600 mm.

What will stay the same

• Block and mortar composition.

#### SHEET METAL

What will change

 Designation from "gage" to millimeters.

What will stay the same

Thickness, which will be soft converted to hundredths of a millimeter.

In specifications, use millimeters only or millimeters with the gage in parentheses.

#### CONCRETE

What will change

Strength designations from "psi" to megapascals, rounded to the nearest 5 megapascals per ACI 318M, such as: 2500 psi to 20 Mpa; 3000 psi to 25 MPa; 3500 psi to 25 Mpa; 4000 psi to 30 Mpa; 4500 psi to 35 Mpa; 5000 psi to 35 Mpa. The amount of rounding will depend upon the use of the concrete.

What will stay the same

• Everything else.

#### REBAR [revised 10/95]

What will change

• Rebars will probably remain the same size but be given new metric designations as follows: #3 to #10M, #4 to #13M, #5 to #16M, #6 to #19M, #7 to #22M, #8 to #25M, #9 to #29M, #10 to #32M, #11 to #36M, #14 to #45M, and #18 to #57M. Call the Concrete Reinforcing Steel Institute for details: 708-517-1200.

What will stay the same

Concrete.

#### **GLASS**

What will change

• Cut sheet dimensions from feet and inches to millimeters.

What will stay the same

 Sheet thickness, which can be rolled to any dimension and is often rolled in millimeters now. See ASTM C1036.

#### **PIPE**

What will change

• Nominal pipe and tubing designations from inches to millimeters.

What will stay the same

• Pipe cross sections.

Pipes and fittings are produced in decimal inch dimensions but named in rounded inch dimensions as a matter of convenience. A 2-inch pipe has neither an inside nor an outside diameter of 2 inches, a 1-inch fitting has

no exact 1-inch dimension, and a 1/2-inch sprinkler head contains no 1/2-inch dimension anywhere, so there is no need to "hard" convert pipes and fittings to rounded metric dimensions. Instead, they will not change size but simply be renamed in metric as follows: 1/8" = 6 mm; 3/16" = 7 mm; 1/4" = 8 mm; 3/8" = 10 mm; 1/2" = 15 mm; 5/8"= 18 mm; 3/4" = 20 mm; 1" = 25 mm; 1-1/4" = 32 mm; 1-1/2" = 40 mm; 2" = 50 mm; 2-1/2" = 65 mm; 3" = 80 mm; 3-1/2" = 90 mm; 4" = 100 mm; 4-1/2" = 115 mm; and 1" = 25 mm for all larger sizes. See the July-August 1993 *Metric in Construction* newsletter for more information.

#### **ELECTRICAL CONDUIT**

What will change

Nominal conduit designations from inches to millimeters.

What will stay the same

• Conduit cross sections.

Electrical conduit is similar to piping: it is produced in "soft" decimal inch dimensions but identified in nominal inch sizes. Neither nonmetallic nor metallic conduit will change size; they be relabeled in metric as follows: 1/2" = 16 (mm), 3/4" = 21; 1" = 27; 1-1/4" = 35; 1-1/2" = 41; 2" = 53; 2-1/2" = 63; 3" = 78; 3-1/2" = 91; 4" = 103; 5" = 129; 6" = 155. These new metric names have been assigned by the National Electrical Manufacturers Association.

#### **ELECTRICAL WIRE**

What will change

• Nothing at this time.

What will stay the same

• Existing American Wire Gage (AWG) sizes.

#### STRUCTURAL STEEL

What will change

- Section designations, from inches to millimeters and from pounds per foot to kilograms per meter, in accordance with ASTM A6M.
- Bolts, to metric diameters and threads per ASTM A325M and A490M.

What will stay the same

Cross sections.

Like pipe and conduit, steel sections are produced in decimal inch dimensions (with depths varying by weight) but are named in rounded inch dimensions. Metric names for equivalent sections are converted and rounded to the nearest 10 mm. Thus, a 10-inch section is relabeled as a 250 mm section and a 24-inch section is relabeled as a 610 mm section.

# Appendix C Detail Revision/Deletion Recommendation Form

Name:		
Code:		
Address:		
Phone:		
e-mail:		
Detail Name	e:	
Recommend	dation (Check one): Revise Delete	
Reason:		
	th additional pages if more space is required.	
Mail to:	U.S. Army Engineer Research and Development Center, Waterways Experiment Station Tri-Service CADD/GIS Technology Center CEWES-ID-C/Spangler	

3909 Halls Ferry Road Vicksburg, MS 39180-6199

#### REPORT DOCUMENTATION PAGE

Form Approved OMB No. 0704-0188

Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503.

1.	AGENCY USE ONLY (Leave blank)	2. REPORT DATE June 1999	3. REPORT TYPE AND DA Report 1 of a series	
4.	TITLE AND SUBTITLE CADD Details Library; Repor	5. FUNDING NUMBERS		
6.	AUTHOR(S) Tri-Service CADD/GIS Techn	ology Center		
7.	PERFORMING ORGANIZATION NAM U.S. Army Engineer Research Waterways Experiment Station 3909 Halls Ferry Road, Vicks	and Development Center		8. PERFORMING ORGANIZATION REPORT NUMBER  Technical Report CADD-93-1
9.	SPONSORING/MONITORING AGENC	CY NAME(S) AND ADDRESS(ES)		10. SPONSORING/MONITORING AGENCY REPORT NUMBER
11.	SUPPLEMENTARY NOTES Available from National Tech	hnical Information Service, 528	85 Port Royal Road, Spring	gfield, VA 22161.
12	Approved for public release;			12b. DISTRIBUTION CODE
	a seasoned draftsman might require this effort has easily been reduce sheet of 20 details can be constitutions. By any measure, the	teed to less than 15 hr. By emploructed in less than 10 min and, development and reuse of CAI to the CADD Details Library was the former Architectural Autom g Group (AAFWG), did not exampletely new details. The AAT	evelop a sheet of construct oying the proposed CADD in many cases, require only DD details represent a cons as developed by collecting ation Task Group (AATG) pend design funds to hire a	ion details. By using CADD, Details Library, an entire y minor project-specific modi-iderable time-saving tool. existing details within the Denow renamed the Architectural architect/engineer or use in-anized existing details into a
14.		onstruction Details etails		(Continued)  15. NUMBER OF PAGES 359  16. PRICE CODE
17.	SECURITY CLASSIFICATION OF REPORT UNCLASSIFIED	18. SECURITY CLASSIFICATION OF THIS PAGE UNCLASSIFIED	19. SECURITY CLASSIFICA OF ABSTRACT	20. LIMITATION OF ABSTRACT

#### 13. (Concluded).

To further simplify the use of the details library, the AAFWG tasked the Tri-Service CADD/GIS Technology Center (the Center) to develop an icon-driven software retrieval system. Developed with MDL and AutoLISP programming, the retrieval software will work on UNIX and DOS Intergraph platforms and AutoCAD DOS systems.

Typically, detailing on a design project does not begin prior to the 35-percent design phase. At the 35-percent phase, the designer has defined the building's structure and envelope requirements and is ready to begin selecting typical project details.

After reviewing the generic details in hardcopy format and identifying usable details, the designer/draftsman initiates the CADD Detail Manager program. The designer scrolls through the details listing, identifies the desired detail, reviews it within the display icon, and then places it on the details sheet. The retrieval program provides a rectangular box (representing the detail's dimensions) that may be dragged within the drawing file and placed by snapping to any of the grid intersection points on the provided details sheet. The detail is automatically placed, and the process is repeated until the entire sheet is filled. Simple modifications to the details to meet specific job requirements complete the sheet. The designer may also call up the details routine while in any design file, thus enabling detail placement anywhere within a set of drawings.

The CADD Details Library should always be considered a "living" document. This means the library may change as often as twice a year. The Center will occasionally announce a *Call For Details*, giving agency designers an opportunity to implement the format in their everyday work habits. After the details are collected, each Center Field Working Group will meet to review and assemble a new generation of the CADD Details Library. The Center will continue to distribute the new libraries and retrieval software. Through evolution, the library will grow to include all the design disciplines with cost incurred only for technical review, reproduction, and distribution.